

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20289-00-00
Spot: SW Sec/Twnshp/Rge: 2-25S-31W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: CUMMINGS Well #: 1-2
County: FINNEY Total Vertical Depth: 2725 feet

Operator License No.: 9152
Op Name: MAREXCO, INC.
Address: 3033 NW 63RD ST - STE 151
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2722	0	WITH 200 SX CMT
SURF	8.625	367		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/02/2014 12:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (405) 286-5657

Proposed Plugging Method: PUMP 20 SX CMT & 200# HULLS OR CIBP @ 2600'. TEST CASING TO 700#. PERFORATE 4 HOLES AT 1100'. PUMP 50 SX CMT. PERFORATE 4 HOLES AT 400'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK

WitnessType: NONE

Date/Time Plugging Completed: 09/02/2014 4:30 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

SAND BACK TO 2580' & CAP WITH 3 SX CMT. TEST CASING TO 700#. HOLDING. PERFORATE 4 HOLES AT 1100'. COULD NOT PUMP INTO AT 900#. PERFORATE 4 HOLES AT 400'. RUN TBG TO 1100' & SPOT 50 SX CMT PLUG BACK TO 400'. TOOH WITH TBG. PUMP 180 SX CMT DOWN CASING THROUGH PERFS & UP THE ANNULUS LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2668	2676		

Received
KANSAS CORPORATION COMMISSION
SEP 12 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA NEED FL** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed

[Signature]
9.12.14 CKM

(TECHNICIAN)

RECEIVED

SEP - 3 2014

KCC DODGE CITY