

1050300

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,275-~~0000~~

C SW SW, SEC. 9, T 35 S, R 16 W/E  
660 feet from ~~XXX~~ SE Corner of section line  
4620 feet from ~~XXX~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lease Name McMoran Well # 1

Operator: McCoy Petroleum Corp.

County Comanche

Name & Address One Main Place, Suite 410

Well Total Depth 5782 187.92 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 361

Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30 pm Day: 1 Month: August Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" set at 5781' Perfs 5027-35' PBD 5742'

1st plug sand back to 4975' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 6 sx hulls, 20 sx gel, 60 sx cement, 15 sx gel, 1 sack hulls, and 200 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:45 pm Day: 1 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 5781' Perfs 5027-35' PBD 5742'

1st plug sanded back to 4975' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 6 sx hulls, 20 sx gel, 60 sx cement, 15 sx gel, 1 sack hulls, and 200 sx cement.

Maximum pressure 550 psi and shut in pressure 400 psi

Remarks: They recovered 3650' of 4 1/2" casing. Used Common cement 2% gel 3% cc by Sun  
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION

DATE 8-14-84

AUG 06 1984

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 3069

CONSERVATION DIVISION  
Wichita, Kansas