

To: 1 010061  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,710-0000  
SW SE SW, SEC. 34, T 26 S, R 12 W/E  
330 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5428  
Operator: Graves Drilling Co., Inc.  
Name & Address 910 Union Center  
Wichita, KS 67202

Lease Name Henrichs Well # 1  
County Pratt 144.95  
Well Total Depth 4460 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 307

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:00 pm Day: 26 Month: December Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" at 4459' PRTD 4444' Perfs at 4292-96'; 4134-44'; 4154-58'  
1st plug sand back to 4080' and dump 5 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Robert B. Tarbutton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:25 pm Day: 26 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4080' and dumped 5 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10  
sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 0

Remarks: Recovered 3300' 5 1/2" casing. Used 60/40 Pozmix .6% gel by BJ-Titan  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE JAN 06 1986  
INV. NO. 11840

RECEIVED  
JAN 2 1986  
1-2-86  
CON.

Signed Robert B. Tarbutton  
(TECHNICIAN)