

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-22046-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 34-26S-12W  
330 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: MARDIS Well Number: 5-34  
County: PRATT Total Vertical Depth: 4315 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 10.75 feet: 296 WITH 200 SX CMT  
Production: Size 4.5 feet: 4312 WITH 175 SX CMT  
Liner: Size \_\_\_\_\_ feet: 140.24

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/28/2000 1:45 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 4110' & 4 SX CMT. 1ST PLUG AT 700' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 75 SX CMT. 3RD PLUG AT 40-0' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/28/2000 4:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4162-72, 4176-86, 4190-4200, 4204-14, 4220-30. SANDED BACK TO 4110' AND PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. LOAD HOLE WITH GEL AND SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 700' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 10 2001  
1-10-01  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2340' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

INVOICED  
DATE 1/10/01  
INV. NO. 2001061259

JAN 02 2001

Form 10/01

MP