

8-9-88

To: 1 061126
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,726-0000
NW NW SW, SEC. 7, T 35 S, R 19 W/E
2310 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4145

Lease Name Box Well # 1-7

Operator: Roberts & Murphy Inc.
Name & Address: Box 7125
Shreveport, LA 71107

County Comanche 221.00
Well Total Depth 6800 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 852

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor: Wilson Casing Pulling License Number 3158

Address Woodward, OK

Company to plug at: Hour: 9 a.m. Day: 9 Month: 8 Year: 19 88

Plugging proposal received from Sid Wilson

(company name) Wilson Casing Pulling (phone) 405-256-6023

were: 5 1/2" at 5226 CIBP at 4970' Perfs at 5010-4242' TOC 3670'

RECEIVED
STATE CORPORATION COMMISSION

1st plug pump 1 sx hulls and 30 sx cement to 4200'

2nd plug pump 50 sx cement at 890'

AUG 10 1988

3rd plug pump 40 sx cement at 400'

8-10-88

4th plug pump 10 sx cement at 40'

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 a.m. Day: 9 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pump 1 sx hulls and 30 sx cement to 4200'

2nd plug pumped 50 sx cement at 890'

3rd plug pumped 40 sx cement at 400'

4th plug pumped 10 sx cement at 40'

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3570' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did/did not) observe this plugging.

DATE 8-11-88

Signed Paul A. Luthie (TECHNICIAN)

INV. NO. 21843