

1 010250

APR 10 1987

98R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C N/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,707-0000

SW/4, SEC. 8, T 35 S, R 18 W/E

1980 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3080

Lease Name Oller Well # 1-8

Operator: Jack Exploration, Inc.

County Comanche 188.50

Name & Address P.O. Box 60

Well Total Depth 5800 feet

Sulphur, OK 73086

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 486

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sage Drilling Company, Inc. License Number 5421

Address 202 South St. Francis, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 10 Month: 4 Year: 1987

Plugging proposal received from Kenneth Mayfield

(company name) Crown Consulting (phone) 316-624-0156

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 885'

1st plug at 900' with 50 sx cement, 2nd plug at 520' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6 p.m. Day: 10 Month: 4 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 900' with 50 sx cement,

2nd plug at 520' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

4-21-87
RECEIVED

STATE CORPORATION COMMISSION

INVOICED

(and observe this plugging.

APR 21 1987

DATE 4-22-87

Signed Jack [Signature]
CONSERVATION DIVISION
(TECHNICIAN) Wichita, Kansas

INV. NO. 16607

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date March 16, 1987 month day year

API Number 15-033-20,707-0000 East

OPERATOR: License # 03080 Name Jack Exploration, Inc. Address P.O. Box 60 City/State/Zip SHADON, OK 73086 Contact Person James R. Jack Phone (405) 622-2310 or (405) 622-2319

.Q. N/2 SW/4 Sec. 8... Twp 35S. S, Rg. 18W... 1980 Ft. from South Line of Section 3960 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # Name Nat. yet selected... will call City/State

Nearest lease or unit boundary line 1320 feet County Comanche Lease Name Oiler Well # 1-8 Ground surface elevation 2050 feet MSL

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary X Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Domestic well within 330 feet: yes no Municipal well within one mile: yes no Depth to bottom of fresh water: Depth to bottom of usable water 200 Surface pipe by Alternator 1 X 2

If OWWO: old well info as follows:

Surface pipe planned to be set 60% cond., 400% surface Conductor pipe required Projected Total Depth 5800 feet Formation Mississippian Limestone

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 3/11/87 Signature of Operator or Agent Title President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. This Authorization Expires 9-13-87 Approved By 3-13-87

SPUD 3-28-87 450' + 8 5/8" DK

.Q. N/2 SW/4 Sec. 8... Twp 35S. S, Rg. 18W... East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ B... Anhy... 800... 900... feet depth with 50... sxs of 60/40 6% Gel. 2nd plug @ 30' below surf... 980 feet depth with 50... sxs of 30/20 6% Gel. 3rd plug @ 40' top surf... 40'... feet depth with 10... sxs of 30/20 6% Gel. 4th plug @ top surf... 0'... feet depth with 10... sxs of 30/20 6% Gel. 5th plug @ ... feet depth with ... sxs of 30/20 6% Gel. (2) Rathole with 15... sxs (b) Mousehole with 10... sxs

Handwritten log table with columns: PUSHER, TD, SURFACE PIPE, ANHYDRITE, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @, 2nd PLUG @, 3rd PLUG @, 4th PLUG @, RAT HOLE CIRCULATED W/, MOUSE HOLE CIRCULATED W/, WATER WELL PLUGGED W/

Handwritten notes: CEMENT COMPANY Fall 60/40 w/ 6% gel, TECHNICIAN Jack went, Rich gave orders

RECEIVED STATE CORPORATION COMMISSION APR 21 1987 4-21-87 CONSERVATION DIVISION Wichita, Kansas