

1070412

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,712 -0000
S SW SE, SEC. 5, T 35 S, R 18 W/EX
330 feet from S section line
1981 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3080

Lease Name Oller Well # 2-5
County Comanche 219.70

Operator: Jack Exploration, Inc.
Name & Address P.O. Box 1816
Liberal, KS 67905-1816

Well Total Depth 6760 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 455

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 12 Month: 9 Year: 19 87

Plugging proposal received from Ken Turner

(company name) H-30 Drilling Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2004'
Anhydrite 1050-60'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 30' below base of surface casing

with 50 sx cement, 3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3 p.m. Day: 12 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1040' with 50 sx cement,

2nd plug at 485' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
COMMISSION

SEP 15 1987

Remarks: Used 60/40 Pozmix 6% gel by Western.
(if additional description is necessary, use BACK of this form)
Wichita, Kansas

INVOICED
I hereby do not observe this plugging.

DATE 9-17-87

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 18141

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

AMENDED INTENT

NOTICE OF INTENTION TO DRILL

*CORRECTED

(see rules on reverse side)

Expected Spud Date... August 20, 1987
month day year

API Number 15-033-20, 712-0000
1981

OPERATOR: License # 03080
Name Jack Exploration, Inc.
Address P.O. Box 1816
City/State/Zip Liberal, KS 67905-1816
Contact Person Keith Hill
Phone (316) 624-0156

SW SE Sec. 5 Twp. 35 S, Rg. 18
330 Ft. from South Line of Section
1981 Ft. from East Line of Section

CONTRACTOR: License #
Name unknown - will call
City/State H-30
Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
X Gas Inj Pool Ext Air Rotary
OWWO Expt X Wildcat Cable

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet
County Comanche

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Lease Name Oller Well # 2-5
Ground surface elevation 2050+ feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 200' 150'
Depth to bottom of usable water 200'
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 450'
Conductor pipe required 60'
Projected Total Depth 6800 feet
Formation Arbuckle test

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 8-18-87 Signature of Operator or Agent Title Agent

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X
This Authorization Expires 2-6-88 Approved By 8-19-87 DRIB. R.C.V. 8-6-87

* WAS: SW-SW-SE 2310 FEL

Made in 8-20-87 400'

RECEIVED
9-15-87
SEP 15 1987

SW SW SE Sec. 5 Twp. 35 S, Rg. 18 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. weekdays)

1st plug @ ft. deep... Base Anhydrite or formation with 50 feet of 60/40, 68 gal
2nd plug @ ft. deep... 30' below surface or formation with 50 feet of " " "
3rd plug @ ft. deep... 40' to 0' or formation with 10 feet of " " "
4th plug @ ft. deep... or formation with feet of
5th plug @ ft. deep... or formation with feet of
(b) Mousehole to surface minus 5 feet 10 SX

PUSHER Ken Turner
TD 6760' FORMATION Arb.
SURFACE PIPE 8 3/4" @ 455'
ANHYDRITE 1050' ELEVATION 2004'
STARTING TIME & DATE 12:30 PM
9-12-87
COMPLETION TIME & DATE 3:00 PM
1st PLUG @ 1040 FT. W/ 50 SX
2nd PLUG @ 485 FT. W/ 40 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAI HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Western Co.
TECHNICIAN D.G.
60/40 per 4 legs
If into Arb. more than 50' a
start 50 SX plug w/ cement.
If Chase Group is present -
plug will be pumped 50' below -
50' above it.
D.G.