

12-3

1 051373

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,789-0000

SW NE, SEC. 11, T 35 S, R 17 W/X

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator Liconso # 30431

Lease Name Betty-Jean Well # 1-11

Operator: W.C. Payne

County Comanche 2/9.37

Name & Address 800 United Founders Tower

Well Total Depth 6750 feet

Oklahoma City, OK 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 708

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 3 Month: 12 Year: 19 90

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5725' w/175 sx cement, PBTD 5520', Perfs at 5424-28'

1st plug sand back to 5375' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 3 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 5375' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3800' of casing

(If additional description is necessary, use BACK of this form.)

INVOICED (X) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 1-7-91

INV. NO. 30371

RECEIVED STATE CORPORATION COMMISSION DEC 6 1990 12-6-90