

To: 1 031414
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-033-20,916-0000
APP. W/2 E/2 NE, SEC. 18, T. 35 S, R. 16 W/8
1200 feet from NS section line
930 feet from E section line

TECHNICIAN'S PLUGGING REPORT

10-4

Operator License # 31898

Lease Name Beeley Well # 18-1

Operator: Conlay P. Smith

County Comanche 198.25

Name & Address 1125 17th, Ste. 2360

Well Total Depth 6100 feet

Denver, CO 80202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 506

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 7:45 p.m. Day: 4 Month: 10 Year: 1996

Plugging proposal received from Walter Brown

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 990' with 50 sx cement, 2nd plug at 510' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:45 p.m. Day: 4 Month: 10 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 990' with 50 sx cement,

2nd plug at 510' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE OCT 18 1996

INV. NO. 46717

10-4

Handwritten notes and stamps: 016-6-91, 10-6-96, RECEIVED, 10-18-96

EFFECTIVE DATE: 9-9-96

State of Kansas

DISTRICT # 1

NOTICE OF INTENTION TO DRILL 033-20,916-0000

SGA? Yes Mo

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 09 06 96
month day year

Spot East
Approx W/2 E/2 NE Sec 18 Twp 35 S, Rg 16 XX West

OPERATOR: License # 31898
Name: Conlay, P. Smith
Address: 1125 17th, Suite 2360
City/State/Zip: Denver, Co 80202
Contact Person: Robert P. Ver, 900
Phone: 303-296-1434

1200 feet from South / North line of Section
930 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 30684
Name: Abercrombie RTD, Inc.

County: Comanche
Lease Name: Beeley Well #: 18-1
Field Name: _____

Well Drilled For: Well Class: Type Equipment:
XX Oil Enh Rec Infield XX Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWO Disposal XX Wildcat Cable
Seismic; # of Holes Other
Other _____

Is this a Prorated/Spaced Field? yes XX no

Target Formation(s): Mississippi/Arbuckle
Nearest lease or unit boundary: 350'

Ground Surface Elevation: Unknown EST. 1845 feet MSL
Water well within one-quarter mile: yes XX no

Public water supply well within one mile: yes XX no
Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 180'

* Surface Pipe by Alternate: X 1 X 2
Length of Surface Pipe Planned to be set: 500'

If OWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Length of Conductor pipe required: N/A
Projected Total Depth: 6350'

Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
well farm pond XX other

Directional, Deviated or Horizontal wellbore? yes XX no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Will Cores Be Taken? yes XX no
If yes, proposed zone: 200' Alt I Req

* ALT 1 ONLY IN COMANCHE COUNTY

Exp. 3/4/97

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following _____

KANSAS CORPORATION COMMISSION

RECEIVED

10-9-96

Pusher Walt Brown INIT. En

SPUD DATE 9-22-96 LENGTH SURFACE PLANNED 500'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE _____
SURFACE PIPES 1/8" @ 506 CONDUCTOR _____
ANHYDRITE T- B- ELEVATION _____

TD 6100 FORMATION _____

RAN PIPE 600 DV TOOL 20 ALT II DONE SX Y N

X Arbuckle Plug @ 1786 Ft. W/ 50 SX
Hugh/Council @ _____ Ft. W/ _____ SX
1 Anhydrite Base @ 990 Ft. W/ 50 SX
1/2 Base Anhy. @ _____ Ft. W/ _____ SX
1/2, 1/2 Plug @ _____ Ft. W/ _____ SX
2 Bottom Surface @ 510 Ft. W/ 50 SX
3 40' Plug @ 40-0 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL creat SX (Irr. Well _____ Pond _____)
TECHNICIAN SD DATE 10-3-96 Hauling _____

TYPE OF CEMENT 60/40 Pct 6%

STARTING TIME 7:45 (AM) DATE 10/4/96

COMPLETION TIME 10:45 (AM) DATE 10/4/96

CEMENT COMPANY Allied