

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 151-21578-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Timberline Oil & Gas Corporation OPERATORS LICENSE NO. 9232
4447 South Canyon Road, Suite 1
ADDRESS Rapid City, SD 57702 PHONE # (605) 341-3400

LEASE (FARM) Dietz WELL NO. W-3 WELL LOCATION 715' FEL COUNTY Pratt
3730' FSL

SEC. 32 TWP. 26S RGE. 12 (E) or (W) TOTAL DEPTH 5100' PLUG BACK TD 3926'

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. D-24050

SURFACE CASING SIZE 10 3/4 SET AT 316' CEMENTED WITH 250 SACKS

CASING SIZE 7" SET AT 4502 CEMENTED WITH 400 SACKS

PERFORATED AT Open hole 4502-5100'

CONDITION OF WELL: GOOD _____ POOR X CASING LEAK X JUNK IN HOLE X

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Go in hole with tubing to top of junk
at 3926'. Spot a 100 sack plug of cement. Pull up. Let cement set. Go back
and tag cement. Find free point of 7" casing and cut off 7" casing. Spot a 50
(If additional space is needed use back of form) (over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Approx. morning of November 13, 1990

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

T.L. McCune PHONE # (316) 672-9476
217 South Ninnescah
ADDRESS Pratt, KS 67124

PLUGGING CONTRACTOR Bayse Well Service LICENSE NO. 5670

ADDRESS 517 S. Main - Stafford, KS 67578 PHONE # (316) 234-5235

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Frank Bate President
(Operator or Agent)
11-13-90

DATE: November 9, 1990

sx cement plug below anhydrite at 730' and at base of surface casing and at surface. Or according to KCC recommendations.

12.00

12.00



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
JACK SHRIVER COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

November 16, 1990

Timberline Oil & Gas Corp.
4447 South Canyon Road, Suite 1
Rapid City, SD 57702

Dietz #W-3
3730'FSL-715'FEL 32-26-12W
Pratt County, KS
API No. 15-151-21,578 -0000

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of David P. Williams.
David P. Williams
Production Supervisor

District: #1, 304 W. McArtor
Dodge City, KS 67801
(316) 225 - 6760