

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Ralph Carristock Pipe Pulling Inc.

Complete Address 320 N Park Stafford Kansas

Lease Name Seuche Well No. -1-

Location C-W2-W2-SW Sec. 6 Twp. 26 Rge. 14 (E) (W)^x

County Pratt Total Depth 4502

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Ralph Carristock

Address 320 N Park Stafford Kansas License No. 490

Operation Completed: Hour 9:00 A Day 1 Month 6 Year 68

The above well was plugged as follows:

287 ft of 8 5/8 in surface pipe circulated with cement
4502 ft of 4 1/2 in pipe along with sand up to 4375 and 4 sacks
cement, mud up to 275 and plug a 10 ft rock bridge and 25
sacks cement, mud up to 40 ft, 10 ft rock bridge and
10 sacks cement to surface.

Recovered 3500 ft 4 1/2 in pipe

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. P. Warren
Well Plugging Supervisor

DATE 6/4/68
INV. NO. 7867-W