

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Pratt

Location: SE SE SW Sec. 9 Twp. 26 Rge. 14W (E) (W)

Name of Field: _____ Total Depth: 4560

I have this date completed supervision of plugging of:

Lease Name: Gereke Well No. 1

Operator's Full Name: Gulf Oil Corp.

Complete Address: Box 2233, Wichita, Kans.

Plugging Contractor: Gabbert-Jones rotary

Address: _____ License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 3:45AM Day 31 Month December 1958 Year _____

The above well was plugged as follows:

822' of 8 5/8" surface casing circulated with cement. Hole was filled
to 300' with heavy drilling mud. HOWCO cementing plug with one quarter
sack hulls set at 300'. 78 sack cement top plug. Heavy drilling mud
to 35'. HOWCO plug set at 35' with 12 sack cement from plug to base
of cellar.

Signed: *[Signature]*
Conservation Division Agent

Reviewed: *[Signature]*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 9 T 26 R 14W
BOOK PAGE 6 LINE 34

RECEIVED
STATE CORPORATION COMMISSION
JAN 9 1959
CONSERVATION DIVISION
Wichita, Kansas