

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-151-20,992-0020

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Raymond Oil Co.

Complete Address One Main Place, Ste. 900, Wichita, Kansas 67202

Lease Name Bishop "A" Well No. 1

Location NW SW NW Sec. 13 Twp. 26 Rge. 14W (East) (West)

County Pratt Total Depth 4360'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. Rig #22

Address 617 Union Center Bldg. Wichita, KS. License No. \_\_\_\_\_

Operation Completed: Hour: 2:00A.M. Day: 13 Month: 9 Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

882' of 8 5/8" SP W/550 sks

Total of 105 sks of 50/50 pozmix 4% gel 3% C.C.

50 sks @ 860'

30 sks @ 350'

Bridge & 10 sks @ 40'

10 RH 5 MH Cemented by Allied

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: M. O. D... Conservation Division Agent

DATE 10-30-81

INV. NO. 8218-W

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 151 — 20,992-00-40  
County Number

S. 13 T. 26S R. 14 EX W

Loc. NW SW NW

County Pratt

Operator Raymond Oil Company, Inc.

Address One Main Place, Suite 900, Wichita, Kansas 67202


Well No. 1 Lease Name Bishop "A"

Footage Location 990 feet from (N) (S) line 330 feet from (E) (W) line

Principal Contractor Geologist  
Murfin Drlg. Co. D. V. Davis, Jr.

Spud Date Date Completed Total Depth P.B.T.D.  
9-1-81 9-12-81 RTD 4360'

Directional Deviation Oil and/or Gas Purchaser



Locate well correctly  
Elev.: Gr. 1971'  
DF. KB. 1982'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8	24#	882'		550	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1991

CONSERVATION DIVISION  
Wichita, Kansas

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS  
Oil Gas Water Gas-oil ratio  
bbls. MCF bbls. CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
 Raymond Oil Company, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS,  
 DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Bishop "A" Dry Hole


S 13 T 26 S R 14 <sup>Ex</sup> <sub>W</sub>

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 Mis-Run - Plugged Anchor	4272	4281	<u>LOG TOPS</u>	
DST #2 Mis-Run - Plugged Anchor	4271	4291	Heebner Sh	3661
			Br Lm	3826
			Lansing	3848
			B/KC	4154
DST #3 30-60-30-60 Rec. 80' mud IFP 81/81# - FFP 92-92# ISIP 914# - FSIP 266#	4276	4360	Conglomerate	4234
			Mississippi	4275
			Kinderhook Ch	4312
			Kinderhook Sd	4327
			Kinderhook Sd	4336
			LTD	4359
D & A Plugged 12-13-81				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	RAYMOND OIL COMPANY, INC.  Wm. M. Raymond <small>Signature</small> President Title October 9, 1981 Date
---------------	---