

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Pratt County. Sec. 23 Twp. 27S Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines App. Ctr. NE/4 NW/4
Lease Owner Messman-Rinehart Oil Company
Lease Name Southwestern College Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed May 6, 19 59
Application for plugging filed May 6 19 59
Application for plugging approved May 6 19 59
Plugging commenced May 6 19 59
Plugging completed May 6 19 59
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation Depth to top Bottom Total Depth of Well 3935 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	303'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bottom plug @ 275' with 1/2 sk. hulls
and cemented with 25 sx. through drill pipe,
set top plug @ 35' with 15 sx. cement.
Mud to surface.

RECEIVED
STATE CORPORATION COMMISSION
AUG 7 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Messman-Rinehart Oil Company
Address 518 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
518 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May, 19 59

Barbara J. Scott
Barbara J. Scott Notary Public.

My commission expires December 1, 1960

PLUGGING
FILE SEC. 23 T. 27 R. 11 W
BOOK PAGE 52 LINE 9

NO. 1 SOUTHWESTERN COLLEGE

Well Record

Location: App. C. NE/4 NW/4
Section 23-27S-11W
Pratt County, Kansas

Commenced: April 25, 1959

Completed: May 6, 1959

Operator: Messman-Rinehart Oil Company
518 Petroleum Building
Wichita, Kansas

Elevation: 1777' K/B

Production: D & A

Contractor: Messman-Rinehart Oil Company
518 Petroleum Building
Wichita, Kansas

Casing Record: 10-3/4" @ 303' w/175 ex. cam.

*** LOG ***

Sand	135
Red Bed	303
Shale & Red Bed	378
Shale	1000
Shale & Red Bed	1230
Anhydrite streaks	1275
Shale & Shells	1465
Shale	1520
Lime & Shale	1560
Lime	2050
Lime & Shale	2570
Shale & Lime	2770
Lime & Shale	2955
Lime	3145
Lime & Shale	3588
Lime	3850
Lime & Shale	3900
Lime & Shale	3935 R.T.D.

Sample Tops:

3400' - Heabner (-1623)
3587' - Brown Line (-1810)
3601' - Lensing (-1824)

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.


MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland

Subscribed and sworn to before me
this 20th day of May, 1959.

Barbara J. Scott
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1960



RECEIVED
STAT. CONSERVATION COMMISSION
AUG 7 1959
CONSERVATION DIVISION
Wichita, Kansas