


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 26 Twp. 22s. Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner Wayne Walcher
Lease Name Horstman Well No. 1
Office Address 809 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed March 7 1968
Application for plugging approved 19
Plugging commenced March 8 1968
Plugging completed March 19 1968
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3875' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	254'	none
				4-1/2"	3855'	2778.47'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3875' - 3550' - sand
3550' - 3502' - 4 sacks cement
3502' - 250' - mud
250' - 240' - rock bridge
240' - 165' - 25 sacks cement
165' - 40' - mud
40' - 30' - rock bridge
30' - base - 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Santa-Fe Pipe & Supply, Inc.,
Address Box 562, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
T. L. Nutt (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *T. L. Nutt*
Box 562, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30 day of March 19 68

My commission expires July 31, 1970
Mary M. Luesener
Notary Public.

15-185-30364-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COPY

COMPANY WAYNE E. WALCHER

SEC. 26 T. 22 N. 14W
LOC. SE NE SW

FARM Horstman NO. 1

TOTAL DEPTH 3875

COMM. 11-14-66

COMP. 11-21-66


BHPT OR TREATED

CONTRACTOR Graves Drlg.

ISSUED 4-22-67

COUNTY Stafford

KANSAS



CASING

20 10
15 8 5/8" @ 254' w/250 sx
12 6
13 4 1/2" @ 3850' w/150 sx

ELEVATION 1936 KB

PRODUCTION DRY/ARB

FIGURES INDICATE BOTTOM OF FORMATIONS

TORS: SCOUT

0 - 220 Sand

Anhydrite 826

220 - 1050 Red bed & shale

Heebner 3318

Brown Lime 3450

1050 - 1628 Shale & shells

Lansing 3462

Conglomerate 3747

1628 - 3085 Lime & shale

Viola 3763

3085 - 3422 Lime

Simpson Shale 3800

3422 - 3540 Lime & shale

Arbuckle 3849

3540 - 3741 Lime

3741 - 3760 Lime & shale

3760 - 3791 Chert

3791 - 3875 Shale

3875 Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
MAR 8 - 1968
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves
President

STATE OF KANSAS)

BUTLER COUNTY)

SS:

Subscribed and sworn to before me, a Notary Public, this 30th of November, 1966.

Betty Brant
Betty Brant Notary Public

My commission expires:
April 30, 1967

RECEIVED
RECEIVED

MAR 6 1968

Santa Fe Pipe & Supply
Santa Fe Pipe & Supply