

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 26 Twp. 22S Rge. 14W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Leban Oil Producers & Aurora Gasoline Co.
Lease Name Stewart Well No. 1
Office Address 505 Orpheum Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-8 19 55
Application for plugging filed 5-8 19 55
Application for plugging approved 5-8 19 55
Plugging commenced 5-8 19 55
Plugging completed 5-8 19 55
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Red Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3909 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	247'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with Rotary Mud to 240'.
Plugged with 1/2 sk hulls mixed with
20 sks cement. Rotary mud to 40'.
Plug with 1/2 sk hulls and 10 sks
cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leban Drilling Company
Address 505 Orpheum Bldg., Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Norma D. Sisson (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norma D. Sisson
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 19 55

Norma D. Sisson
Notary Public.

My commission expires April 20, 1959

PLUGGING
SEC 26 T22S R14W
PAGE 17 LINE 28

MAY 12 1955
5-12-55
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY: Aurora Gasoline Company &
 Leben Oil Producers
 CONTRACTOR: Leben Drilling Company
 FARM: Stewart
 LOCATION: NW NW SW Sec. 26-22S-14W
 Stafford County, Kansas
 COMMENCED: April 25, 1955
 COMPLETED: May 8, 1955

0	120	Surface Sand
120-224	224	Sand
224	248	Blue shale
248	310	Blue shale
310	375	Sand
375	798	Shale, redbed
798	835	Shale, redbed
835	865	Anhydrite
865	1220	Shale, redbed
1220	1530	Shale, sand
1530	1782	Shale, sand
1782	1934	Lime, shale
1934	2071	Lime, shale
2071	2226	Lime, shale
2226	2367	Lime, shale
2367	2407	Lime, shale
2407	2495	Lime, shale
2395	2670	Lime, shale
2670	2846	Lime, shale
2846	2952	Shale, lime
2952	3075	Shale, lime
3075	3162	Lime, shale
3162	3227	Lime, shale
3227	3327	Lime, shale
3327	3430	Lime, shale
3430	3514	Top Kansas City, 3481'
3514	3541	Lime
3541	3608	Lime
3608	3617	Lime
3617	3658	Lime
3658	3680	Lime
3680	3707	Lime
3707	3757	Lime, shale
3757	3771	Lime, shale
3771	3810	Viola Lime
3810	3820	Viola Lime
3820	3860	Shale
3860	3879	Shale, lime
3879	3891	Dolomite
3891	3909	Dolomite, Rotary Total Depth

Set 8 5/8" surface at 247'

I, Norma D. Sisson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Stewart #1, NW NW SW Sec. 26-22S-14W, Stafford County, Kansas, as reflected by the files of the Leben Drilling Company.

LEBEN DRILLING COMPANY

Norma D. Sisson
Norma D. Sisson

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 11th day of May, 1955.

Norma D. Sisson

Notary Public
RECEIVED
STATE CORPORATION COMMISSION

My commission expires

Apr 20 - 1959

MAY 12 1955

PLUGGING
WELL NO. 26-22S-14W
PAGE 17 OF 38

CONSERVATION DIVISION
Wichita, Kansas