

15-151-10934-00-02

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County. Sec. 36 Twp. 26S Rge. 13 (E//) (W)

Location as "NE/CNW/SW" or footage from lines NE/NE/NW

Lease Owner Forbes Casing Pulling Co.

Lease Name W.H. Geissler Well No. #1

Office Address Box 221, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed Yes 19\_\_

Application for plugging approved Yes 19\_\_

Plugging commenced 9-10 1958

Plugging completed 9-14 1958

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W.L. Lackamp

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4346' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"		
				4 1/2"		2,022'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into T.D. 4346'.  
Plugging started 9-10-58. Finished 9-14-58.  
Plugged off bottom and sanded back to 3955'. Dumped 5 sacks cement.  
Worked and shot pipe. Circulated and spotted 60 bbls oil. Shot 4 1/2"  
casing at 2,022'. Pulled pipe out of hole and plugged well as follows:  
Mudded to 350'. Set rock bridge and dumped 20 sacks cement. Filled  
hole with mud. Set rock bridge and capped well with 10 sacks cement.  
Well completed.

OCT 11 1958  
10-11-58

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J.O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes  
Box 221, Great Bend, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1958

My commission expires November 8, 1960 Betty L. Edmond Notary Public.

PLUGGING  
FILE SEC 36 T 26 R 13W  
BOOK PAGE 128 LINE 19

15-151-10934-00-02

SHELL-W. H. GEISSLER #1  
NE NE NW Section 36-26S-13W  
Iuka-Carmi Field  
Pratt County, Kansas

Casing Record

8-5/8" cem 808 with 400 sax; circulated.  
4 1/2" cem 4336 with 300 sax; perforated 4252-64  
& 3966-70.

0 - 30 surface soil & sand  
65 shells & sand  
192 sand  
250 sand & shale  
585 red bed & shells  
620 sand  
770 red bed & shells  
809 anhydrite & red bed  
1320 shale & shells  
1590 salt, shale & shells  
1925 shale & shells  
2014 shale & lime  
2100 broken lime  
2160 lime  
2241 broken lime  
2326 lime  
2385 lime & shale  
2435 lime  
2630 lime & shale  
2660 shale  
3075 shale & lime  
3095 shale  
3245 lime & shale  
4070 lime  
4087 lime & shale  
4110 lime, chert & shale  
4119 lime & chert  
4146 lime SLC  
4169 chert, lime & shale  
4184 lime & chert  
4195 chert  
4209 shale, lime & chert  
4217 lime & chert  
4228 shale  
4236 sand & sandy lime  
4249 shale & dolomite  
4258 sand & dolomite  
4276 sand & shale  
4282 shale  
4286 dolomite  
4310 shale, dolomite & sand  
4326 dolomite w/ shale  
4331 shale  
4336 dolomite w/ chert  
4336=4339 SLC  
4346 dolomite T.D.  
3988 P.B.

Formation Tops:  
Topeka 3197  
Lansing-Kansas City 3732  
Viola 4183  
Simpson 4219  
Arbuckle 4334

Plug Back Record:  
Set GIBP @ 4290 & capped with 1 sack  
cement to 4280.  
Set GIBP @ 4000 & capped with 1 sack  
cement to 3988

Centralizers on 4 1/2" casing at 3745,  
4865, 4895 & 3950.

Initial Production (Arbuckle) - I.c. 5008 BO,  
no water 24 hours (drawdown) 3-21-44.  
Last Test (Arbuckle) - 5 BO 740 BW 24 hours  
12-4-56.

Initial Production (Simpson) - Pumped 6 BO &  
60 BW 24 hours 3-19-57.  
Last Test (Simpson) - 1 BO & 16 BW 24 hours  
12-8-57.

Initial Production (LKC) - Pumped 2 BO & 29  
BW 24 hours 1-12-58.  
Last Production (LKC) - Pumped 18 bbls water,  
no oil, 24 hours 5-4-58.

RECEIVED  
CONSERVATION COMMISSION

SEP 9 1958

CONSERVATION DIVISION PLUGGING  
Wichita, Kansas FILE SEC. 36 T. 26 R. 13 W  
BOOK PAGE 128 LINE 19