


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County, Sec. 5 Twp. 34 Rge. 14 (E) (W) x
Location as "NE/CNW/SW" or footage from lines NW SW NW
Lease Owner Specter Pipe & Supply Co., Inc.
Lease Name Davis Ranch Well No. "O" 1
Office Address Box 169 Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 6-26-73 19____
Plugging completed 7-6-73 19____
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4879' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	4880'	4028.13'
				13 3/8"	201'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 4820'. Mixed and ran 3 sacks cement thru dump bailer.
Mudded hole to 120' - set 20' rock bridge. Filled hole with 5 yards ready-mix to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1973
7-9-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7 day of July, 19 73

Sidney D. Miller
Notary Public.

My commission expires



Davis Ranch "O" #1
NW SW NW Sec 5-34S-14W

Drillers Log

0-205	Shale & Shells
205-280	Red Bed & Shale
280-865	Red Bed
865-1640	Shale & Shells
1640-2005	Shale & Lime
2005-2300	Lime
2300-2460	Lime & Shale
2460-2535	Lime
2535-4215	Lime & Shale
4215-4285	Lime
4285-4345	Lime & Shale
4345-4715	Lime
4715-4750	Lime & Shale
4750-4880	Lime

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1972
7-14-72
CONSERVATION DIVISION
Wichita, Kansas