

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 5 Twp. 35-S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines CSE/4 NW/4 NE/4

Lease Owner Barbara-Amerada

Lease Name Barbara-Amerada Bank Unit Well No. 1

Office Address 322 Central Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 16, 1955

Application for plugging filed May 19, 1958

Application for plugging approved May 20, 1958

Plugging commenced June 9, 1958

Plugging completed June 16, 1958

Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W.L. Lackamp, Jr.

Producing formation None Depth to top Bottom Total Depth of Well 4940 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	286'	None
				5 1/2"	4940'	3495'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rock bridge set at 4850'. Filled with gravel from 4850' to 4768'.  
Mixed and dumped with bailer 6 sacks cement. Top of cement at 4715'. Shot casing at 3495'. Pulled 40 joints or approx. 1720'. Mixed and circulated 10 sacks of Margocel mud at 1775'. Good circulation of mud in cellar. Finished pulling casing. 8-5/8" surface casing set at 286' cemented top to bottom. Bailed mud to 286', set 10' rock bridge from 286' to 276'. Mixed and dumped 25 sacks cement. Filled with mud to 40' below base of cellar. Rock bridge from 40' to 30'. Mixed and dumped 10 sacks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Arnett Casing Pulling Company  
Address Hoisington, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
L.W. Davidson (employee of owner) or (owner/operater)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L.W. Davidson  
322 Central Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 23rd day of June, 1958

Mildred Fisher Notary Public.

My commission expires March 2, 1961

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 24 1958  
6-24-58  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 5 T 35 R 12W  
BOOK PAGE 101 LINE 23

Barbara Oil Company  
 Barbara-Amerade Bank Unl. Well #1  
 Total Depth 4940'  
 Rotary Comm. 3/28/55  
 Rotary Comp. 4/20/55  
 Cable Tool Comp. 5/29/55  
 Contractor R. C. Patton Co.,

Location; SE/4, N 1, NE/4, Section 5-  
 T35S-R12W Barber County, Kansas.  
 CASING RECORD  
 8 5/8" Casing at 286'  
 Cemented with 175 Sack Cement  
 5 1/2" Casing at 4940'  
 Cemented with 250 Sacks Cement

Surface Clay 30  
 Red Beds 100  
 Sand 110  
 Red Shale & Shells 286  
 Red Bed & Shells 1135  
 Shale & Shells 1770  
 Anhydrite & Shale 2010  
 Lime & Shale 3270  
 Lime 3284  
 Lime & Shale 3508  
 Sand & Shale 3542  
 Lime & Shale 3690  
 Sand & Shale 3740  
 Lime & Shale 4170  
 Sand 4256  
 Lime & Shale 4388  
 Lime 4666  
 Lime & Shale 4775  
 Cored 4865  
 Conglomerant 4878  
 Cherty Lime 4940  
 Total Depth 4949

TOPS:  
 All tops from Kelly Bushing 10' above  
 Ground Level.  
 Elgin Sand 3672  
 Base Oread 3920  
 Stalnaker 4172  
 Chester Sand 4792  
 Mississippian 4805

STATE OF Kansas COUNTY OF Sedgwick ss,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

R. C. PATTON CO.,

BY Robert W. Patton

Subscribed and sworn to before me this 2nd day of June 1955

A. P. Hendrick  
 Notary Public.

My Commission Expires Oct 4th 1956.

RECEIVED  
 STATE CONSERVATION COMMISSION  
 MAY 20 1955  
 5-20-58  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC. S. T. 35 R. 12 W  
 BOOK PAGE 101 LINE 23