

15-185-11351-00-00

Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

All Information Completely  
Required Affidavit  
or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 26 Twp. 22S Rge. 14 (W)

Location as "NE/CNW/SW" or footage from lines C-N/2 NE NE

Lease Owner Morgenstern Oil Operations

Lease Name Dohrman Well No. 3

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-9-63 19

Application for plugging filed 8-8-63 19

Application for plugging approved 8-8-63 19


Plugging commenced 8-8-63 19

Plugging completed 8-9-63 19

Reason for abandonment of well or producing formation None

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Elzing

Producing formation Depth to top Bottom Total Depth of Well 3821 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	300	8 5/8	300	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

The hole was filled with heavy mud to 280'  
plug, 2 1/2 sacks hulls and 25 sacks cement.  
Mudded hole to 40' 1/3 sack hulls, plug and  
10 sacks cement. Rat hole plugged with 5  
sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 21 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Terrel Drilling and Producing  
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
Joe K. Branum (owner or operator) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum  
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 19 63

My commission expires 12-12-66

L. Lee Simpson  
Notary Public.

W E L L L O G

15-185-11351-00-00

OPERATOR: Morgenstern Oil Operations  
Box 2526  
Wichita, Kansas

CONTRACTOR: Terrel Drilling and Producing  
Box 606  
Russell, Kansas

LEASE: Dohrman *B*

COMMENCED: July 30, 1963

LOCATION: C-N/2-NE NE Sec.26-R22S-14W  
Stafford County, Kansas.

COMPLETED: August 9, 1963

RECEIVED  
STATE CORPORATION COMMISSION

AUG 21 1963

CONSERVATION DIVISION  
Wichita, Kansas

FORMATIONS & DEPTHS

Sand and Clay	90	Lime	2025
Sand and Shale	300	Lime and Shale	3365
Shale	350	Sandy Lime	3500
Red Bed	500	Lime and Shale	3605
Shale and Shells	1140	Lime	3650
Lime and Shale	1885	Lime and Shale	3750
		Lime and Chert	3787
		Lime (R.T.D.)	3821

STATE OF KANSAS )  
                          ) SS.  
COUNTY OF RUSSELL)

Joe K. Branum, owner of Terrel Drilling and Producing, being first duly sworn on oath says: "That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct."

*Joe K. Branum*  
\_\_\_\_\_  
Joe K. Branum

Subscribed and sworn before me this 9th day of August, 1963.

*L. L. Simpson*  
\_\_\_\_\_  
Notary Public                      Russell County

My Commission Expires: December 12, 1966