

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-151-21898-00-00

API NUMBER                      SPUD DATE 9-14-88

LEASE NAME HOLLAND

WELL NUMBER B-1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

4290 Ft. from S Section Line

2820 Ft. from E Section Line  
 SE NE NW

SEC. 8 TWP. 27S RGE. 11 ~~20W~~ (W)

COUNTY PRAIRIE

LEASE OPERATOR A & A DISCOVERY INC.

ADDRESS P O BOX 156 HILL CITY, KS. 67642

PHONE# (913) 674-2768 OPERATORS LICENSE NO. 5929

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed                     

Plugging Commenced 7-15-91

Plugging Completed 7-17-91

The plugging proposal was approved on JULY 15, 1991 (date)

by RICHARD LACEY GAVE BHP ORDERS STEVE PFEIFER ON LOC. (KCC District Agent's Name).  
FOR TOP HOLE PLUG.

Is ACO-1 filed? YES If not, Is well log attached?                     

Producing Formation                      Depth to Top                      Bottom                      T.D. 4023

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	203	10 3/4	203	0
		0	762	8 5/8	762	0
		0	4096	4 1/2	4096	2334 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
7-15-91: SANDED TO 3760 FT. PLUS 4 SX CEMENT ON TOP OF SAND. 7-16-91: SHOT OFF CASING AT 2334 FT. PULLED AND LAYED DOWN CASING. 7-17-91: B J TITAN TOP HOLE PLUGGED 300# HULLS, 10 GEL, 50 SX, 10 GEL, 100# HULLS, 8 5/8 PLUG, 100 SX CEMENT, 60 40 POZ, 6% GEL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRAIRIE WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRAIRIE, KANSAS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A & A DISCOVERY, INC.

STATE OF KANSAS COUNTY OF PRAIRIE, ss.


JUDY BERRY

PLUGGING CONTRACTOR:

(Employee of ~~XXXXXXXXXXXXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) To Public, Inc.



STATE CORPORATION COMMISSION SUBSCRIBED AND SWORN TO before me this 6th day of August, 19 91

Dorothy M. Ferguson  
 Notary Public

AUG 07 1991

CONSERVATION DIVISION  
 Wichita Kansas

My Commission Expires February 6, 1993