

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,927-60-00

LEASE NAME Holland

WELL NUMBER A-3

3075' Ft. from S Section Line

3715' Ft. from E Section Line

SEC. 8 TWP. 27 RGE. 11 (E) or (W)

COUNTY Pratt

Date Well Completed 4-24-89

Plugging Commenced 4-24-89

Plugging Completed 4-25-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A & A Discovery, Inc.

ADDRESS P.O. Box 156 Hill City, KS 67642

PHONE#(913) 674-2768 OPERATORS LICENSE NO. 4748

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-21-89 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @600' w/50 sacks cement thru drill pipe

Next Plug: @280' w/40 " " " " "

Top Plug: @ 40' w/10 " " " " "

15 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A & A Discovery, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson


(Employee of Operator) or ~~XXXXXX~~ of

above-described well, being first duly sworn, says: That I have knowledge of the facts, statements, and matters herein contained and of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530

APR 28 1989



CONSERVATION DIVISION
Wichita, Kansas

27 day of April, 1989
Dorothy M Hague
Notary Public

My Commission Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: April 18, 1989
DATE COMPLETED: April 25, 1989

A & A Discovery, Inc.
HOLLAND #A-3
Approx. SW SE NW
Sec. 8, T27S, R11W
Pratt County, Ks.

0 - 219' Surface Soil, Clay & Sand
219 - 256' Shale
256 - 575' Red Bed
575 - 599' Anhydrite
599 - 1689' Shale
1689 - 2843' Lime & Shale
2843 - 3448' Lime
3448 - 3649' Shale & Lime
3649 - 4050' Lime
4050' RTD

ELEVATION: 1819 K.B.

Surface Pipe: Set used
10-3/4" 32# pipe @255'
w/175 sacks 60/40 pozmix
2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 27 day of April 1989.



Dorothy M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

APR 29 1989

CONSERVATION DIVISION
Wichita, Kansas