

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,990-00-00

LEASE NAME HOLLAND

WELL NUMBER B-2

 Ft. from S Section Line

 Ft. from E Section Line

SE NE NW
SEC. 8 TWP. 27S RGE. 11 ~~XXXX~~ (W)

COUNTY PRATT

Date Well Completed 4-16-90

Plugging Commenced 7-11-91

Plugging Completed 7-24-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A & A DISCOVERY INC.

ADDRESS P O BOX 156 HILL CITY, KS. 67642

PHONE# (913) 674-2768 OPERATORS LICENSE NO. 5929

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on JULY 15, 1991 (date)

by STEVE PFELFER ON LOCATION (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4026

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	757	8 5/8	757	0
		0	4020	4 1/2	4020	3006 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
7-11-91: SAND TO 3860+ 4 SX CEMENT. 7-12-91: SHOT OFF AT 3006FT, PULLED 88 JTS OF CASING.
7-17-91: B J TITAT TOP HOLE PLUGGED WITH 300# hulls, 10 gel, 50 sx cement, 10 gel, 100# hulls, 8 5/8 plug, 100 sx cement, 60 40 poz, 6% gel. 7-23 and 24, 1991: RIGGED UP, RAN TUBING IN WELL TO PUMP PLUGS. RAN 25 JTS OF TUBING TO 778 FT. SPOTTED 50 SX ABOVE PLUG. PULLED UP TO 344 FT.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A & A DISCOVERY INC.

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR

(Employee of ~~XXXXXXXXXXXXXXXXXXXX~~)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) P.O. PWS, Inc.



RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 91

AUG 07 1991

CONSERVATION DIVISION
Wichita Kansas

My Commission Expires: February 6, 1993
Dorothy M. Furgason
Notary Public

PUMPED A 25 SACK PLUG, PULLED OUT OF THE HOLE AND PULLED ON JOINT OF 8 5/8, AND
LAYED IT DOWN. ON JULY 24, 1991, RAN 280 FT OF 2 3/8 TUBING AND TAGGED PLUG, CAME OUT OF
THE HOLE WITH TUBING AND LAYED DOWN. B J TITAN PUMPED 150 SX. CEMENT DOWN THE 8 5/8.
TOP OF CEMENT WAS ELEVEN FT. DOWN FROM SURFACE ON 7-29-91.

1991 JUL 29 11 11 AM
BJ TITAN
150 SX CEMENT
8 5/8