

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

PRATT County. Sec. 7 Twp. 27S Rge. (E) 11 (W)
Location as "NE/CNW%SW%" or footage from lines C NW NW
Lease Owner LARSEN, MADERA & HARRISON
Lease Name MAAS Well No. 1
Office Address 1000 FIDELITY UNION TOWER, DALLAS, TEXAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed Nov. 28, 1966
Application for plugging filed (PHONE 11/28/66) Nov. 30, 1966
Application for plugging approved Nov. 28, 1966
Plugging commenced Nov. 28, 1966
Plugging completed Nov. 28, 1966
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4454 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	334	8-5/8	334	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 250 FEET. SET FIRST PLUG AT 250 FEET WITH 1/2 SACK HULLS AND 25 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG AT 40 FEET WITH 1/4 SACK HULLS AND 10 SACKS CEMENT. PLUGGED RAT HOLE WITH 2 SACKS CEMENT. JOB COMPLETE 10:00 PM, Nov. 28, 1966.

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1966

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 SUTTON PLACE, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall
830 SUTTON PLACE, WICHITA, KANSAS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 30TH day of NOVEMBER, 19 66

My commission expires FEBRUARY 1, 1968
Barbara J. Layton
BARBARA J. LAYTON Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

RECEIVED

DEC 9 1966

MAAS #1
 C. NW NW SECTION 7-27S-11W
 PRATT COUNTY, KANSAS

COMMENCED: NOVEMBER 16, 1966
 COMPLETED: NOVEMBER 28, 1966

OPERATOR - LARSEN, MADERA & HARRISON

DEPTH	FORMATION	REMARKS
FROM	To	
0	150	SAND
150	334	RED BED AND SHALE
		RAN 13 JOINTS OF 8-5/8" CASING, SET @ 334' w/275 SACKS CEMENT.
334	560	RED BED AND SHALE
560	600	LIME AND SHALE
600	680	SHALE
680	1050	RED BED
1050	1490	SHALE AND RED BED
1490	3165	LIME AND SHALE
3165	3220	SHALE
3220	3664	LIME AND SHALE
3664	4095	LIME
4095	4140	LIME, SHALE AND CHERT
4140	4175	LIME AND CHERT
4175	4205	LIME, SHALE AND CHERT
4205	4240	CHERTY LIME
4240	4262	LIME AND CHERT
4262	4330	LIME AND SHALE
4330	4365	CHERTY LIME
4365	4394	LIME, CHERT AND SHALE
4394	4444	SHALE, LIME AND SAND
4444	4454	SANDY SHALE
4454	TD	DRY AND ABANDONED.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NW NW SECTION 7-27S-11W, PRATT COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 1ST DAY OF DECEMBER, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.