

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 5 TWP. 27S RGE. 11 NE/W
Location as in quarters or footage from lines:
S.W. S.W.

Lease Owner Rupe Oil Co.
Lease Name Shaneline Well No. 1
Office Address P.O. Box 2273/Wichita, KS/
Character of Well (Completed as Oil, Gas or Dry Hole): oil
Date Well Completed 04/04/82
Application for plugging filed 05/18/83
Plugging commenced 05/25/83
Plugging completed 06/07/83
Reason for abandonment of well or producing formation dry

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Lacey/Metz Lacey on top
Producing formation _____ Depth to top _____ bottom _____ T.D. 4117

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	488	none
				4 1/2	4098	3428

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set. Plugged back at 4054

Sand from 4054 to 3900

Dumped 4 sx. cement with dump bailer from 3900 to 3860

5 hull, 20 jell, 50 cement, 15 jell, plug, 100 cement,
60-40 POZ, 2% jell, 3% c.c.

Zimmerman on location

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corp.

STATE OF Kansas COUNTY OF Barker, ss.
Edna J. Morgenstern (employee of ~~owner~~) or (~~owner or operator~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Edna J. Morgenstern
Medicine Lodge, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of June, 1983

Jessie Hamilton
STATE CORPORATION COMMISSION Notary Public.

My Commission expires: April 4, 1986.

JUN 13 1983

CONSERVATION DIVISION
Wichita, Kansas