

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt

County. Sec. 5 Twp. 27 Rge. (E) 11 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. W/2 NW/4 NE/4

Lease Owner Nadel & Gussman

Lease Name White Well No. 1

Office Address National Mutual Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date, well completed December 28 1941

Application for plugging filed " 28 1941

Application for plugging approved " 28 1941

Plugging Commenced " 28 1941

Plugging Completed " 29 1941

Reason for abandonment of well or producing formation Dry hold

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 4510 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	294'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole with mud 4510 to 294', 14# circulated every 500'
Plug set at 294' with 10 sax cement
Filled with mud to 38'
Plug set at 38' with 10 sax cement



5:27 11W
18 44

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....
Address.....

STATE OF Kansas, COUNTY OF Sedgwick, ss.

..... (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)..... *[Signature]*

(Address).....

SUBSCRIBED AND SWORN to before me this 31st day of December, 1941

[Signature]
Notary Public.

My commission expires Dec. 6, 1945.



COMPANY: Madol & Gussman
 CONTRACTOR: Hannum Drilling Company, Inc.
 FARM: White Well #1

LOCATION: C WL NW NE
 Sec. 5-27-11W
 Pratt County, Kans.

COMMENCED: 12-3-41
 COMPLETED: 12-29-41

CASING RECORD

8 5/8" 294' 140 Sax Lohigh

ELEVATION: 1813
 PRODUCTION: D & A

FORMATION	DEPTH	FORMATION	DEPTH
Surface sand & clay	129'	brown lime	3625'
sand	185	shale & lime	3645
redrock	690	lime	3810
redrock & shale	826	brk lime & chert	3906
shale & shells	866	lime	3945
anhydrite	980	lime & shale	4016
anhydrite, redrock, shale	1040	lime	4066
anhydrite & shale	1110	shale	4086
shale & shells	1410	chert & lime	4100
shale & salt	1550	lime & chert	4150
anhydrite	1782	lime	4200
sandy lime	1835	shale	4277
broken sandy lime	2246	lime & chert	4287
broken lime & shale	2680	Cored	4287-94
broken lime & shale	2825	6' recovery	
broken lime	3035	crystalline gry lime, slight	
shale	3059	porosity-slight gas odor	
lime	3070	lime & chert	4350
shale	3088	lime	4393
sandy shale	3103	shale	4397
lime	3319	sand	4403
sandy lime	3336	shale & sand	4466
lime	3370	Arbuckle Dolomite	4468
lime & shale	3468	Dolomite	4610
shale & shells	3500		
shale & lime	3614		
		TOTAL DEPTH	

I hereby certify this to be a correct and accurate log of the above described well as shown by the drilling reports.

Subscribed and sworn to before me this 29 day of

December, 1941.

M. Johnson

Clyde Smalley

 Notary Public

My Commission expires December 6, 1945.

5 : 27 11W
 .18 : 44