


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

PRATT County. Sec. 20 Twp. 27S Rge. 11W (E) (W)
Location as "NE/CNW%SW%" or footage from lines. NW SE SW
Lease Owner BOWERS DRILLING COMPANY, INC.
Lease Name SWISHER Well No. 1
Office Address 1434 WICHITA PLAZA, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed _____ 19____
Application for plugging filed MARCH 29 1965
Application for plugging approved _____ 19____
Plugging commenced MARCH 30 1965
Plugging completed APRIL 3 1965
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4372' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	348'	NONE
				4 1/2"	4372'	3793.07'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4372'	-	4300'	-	SAND
4300'	-	4264'	-	3 SACKS CEMENT
4264'	-	285'	-	BAILED FLUID
285'	-	275'	-	ROCK BRIDGE
275'	-	263'	-	4 SACKS CEMENT
263'	-	200'	-	21 SACKS CEMENT
200'	-	40'	-	MUDDERED HOLE
40'	-	30'	-	ROCK BRIDGE
30'	-	BASE	-	10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

APR 23 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address P. O. BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON
T. L. NUTT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt

P. O. BOX 562, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 5TH day of APRIL, 19 65

My commission expires JULY 31, 1966

Mary M. Guesnier
MARY M. GUESNIER Notary Public.

WELL LOG

COMPANY: Bowers Drilling Company, Inc.
CONTRACTOR: Bowers Drilling Company, Inc.
FARM: Swisher #1
LOCATION: NW SE SW Section 20-27S-11W
Pratt County, Kansas
COMMENCED: November 11, 1964
COMPLETED: November 26, 1964
ELEVATION: 1814 K. B.

0 - 200	Sand	
200 - 545	Redbed	8-5/8" casing set at 350 with 175 sacks cement
545 - 670	Shale and shells	
670 - 1100	Redbed, shale and shells	
1100 - 3728	Lime and shale	
3728 - 4134	Lime	
4134 - 4164	Chert and lime	
4164 - 4245	Lime	
4245 - 4330	Kinderhook-Viola	
4330 - 4367	Viola	
4367 - 4372	Lime	4 1/2" casing set at 4372 with 100 sacks cement
4372	T. D.	

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1965

CONSERVATION DIVISION
Wichita, Kansas

LOG TOPS:

Heebner	3450	B/Kansas City	4020
Douglas Shale	3478	Mississippian	4123
Brown Lime	3639	Kinderhook	4228
Lansing/K. C.	3653	Viola	4324

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Swisher #1 located NW SE SW Section 20-27S-11W, Pratt County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers

Subscribed and sworn to before me, a Notary Public in and for Sedgwick County, Kansas, this 2nd day of December, 1964.

Donna F. Miller
Donna F. Miller, Notary Public

My commission expires May 1, 1966.