

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-22572-00-00

LEASE NAME DAVIS RANCH

WELL NUMBER A-1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

1295 Ft. from S Section Line

4010 Ft. from E Section Line

SEC. 5 TWP. 34 RGE. 14 (E) or (W)

COUNTY BARBER

Date Well Completed 8/19/98

Plugging Commenced 9/20/00

Plugging Completed 11/28/00

LEASE OPERATOR WOOLSEY PETROLEUM CORP.

ADDRESS P.O. Box 168 MEDLINE LODGE KS 67104

PHONE# (316) 886-5606 OPERATORS LICENSE NO. 5506

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 21, 2000 (date)

by DAVID P. WILLIAMS (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? YES

Producing Formation SIMPSON Depth to Top 5262 Bottom 5269 T.O. 5440

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
<u>SIMPSON</u>	<u>oil-water</u>	<u>0'</u>	<u>220'</u>	<u>10 3/4"</u>	<u>220'</u>	<u>-0-</u> NOV 30 2000
		<u>0'</u>	<u>256'</u>	<u>8 5/8"</u>	<u>256'</u>	<u>-0-</u> 11-30-00
		<u>0</u>	<u>5427</u>	<u>4 1/2"</u>	<u>5427</u>	<u>4792'</u> CONSERVATION DIVISION
						Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
FROM SURFACE Pump Down 8 5/8" CASING AS FOLLOWS: 300# COTTON SEED HULLS, 10 SACK GGL, 50 SACK 60/40 POZ MIX + 6% AEL + 10 SACK AEL, 100# COTTON SEED HULLS & 100 SACK SAMG CEMENT. 11/28/00 CEMENT DROPPED 300' INSIDE SURFACE PIPE. FILL W/ READY MIX CONCRETE TO SURFACE.

Name of Plugging Contractor PRATT WELL SERVICE License No. 5893

Address PRATT, KANSAS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WOOLSEY PETROLEUM CORP.

STATE OF Kansas COUNTY OF Barber, ss.

CARL W. DURR (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl W. Durr

(Address) _____

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 2000

Charlotte C. Hoagland
 Notary Public

My Commission Expires: Aug. 2, 2004

STATE OF KANSAS
 NOTARY PUBLIC
 Charlotte C. Hoagland
 My Appt. Exp. 8/2/04

Form CP-1
 Revised 05-98

MB