

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Roberts & Murphy Inc.

ADDRESS P. O. Box 7125, Shreveport, LA. 71107

PHONE# (318) 221-8601 OPERATORS LICENSE NO. 4145

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 2, 1988 (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? yes

Producing Formation none Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	852'	None
				5 1/2	5226'	3589.06'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Pumped 30 sack plug from 4066' to 3856' with cement and rubber plug. Shot pipe @ 3575'. Pumped 50 sack plug from 890' to 740'. Pumped 40 sack plug from 400' to 280'. Pumped 10 sack plug from 40' to 4'. Welded on-  
 (If additional description is necessary, use BACK of this form.) name plate:

Name of Plugging Contractor Wilson Casing Pulling, Inc. License No. nr 608

Address P. O. Box 963 Woodward, Oklahoma 73802

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Roberts & Murphy, Inc.

STATE OF Louisiana COUNTY OF Caddo, ss.

J. Brad Cummings (Employee of Operator) of \_\_\_\_\_ (City or Parish) of \_\_\_\_\_ (State) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. Brad Cummings

(Address) P. O. Box 7125 SHREVEPORT LA

SUBSCRIBED AND SWORN TO before me this 30<sup>th</sup> day of August, 19 88

Myrtle A. Oksenholt  
 Notary Public

My Commission Expires: with life

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

FEB 7 1983

Form CP-4  
Rev. 12-15-80

2-7-83  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Comanche SEC. 7 TWP. 35S RGE. 19 E/W (19)  
Location as in quarters or footage from lines:  
1400' FNL & 2500' FWL


Locate Well  
correctly on above  
Section Platt.

Lease Owner Mesa Petroleum Co.  
Lease Name Box Ranch Well No. #1-7  
Office Address Box 2009, Amarillo, TX 79189  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 10-2-81  
Application for plugging filed 11-29-82  
Plugging commenced 12-23-82  
Plugging completed 12-30-82  
Reason for abandonment of well or producing formation Non-economical

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton  
Producing formation Dry Hole Depth to top 4249' bottom 4286' T.D. 5500'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Toronto	Dry	4249	4286	8 5/8"	657'	None
				4 1/2"	4415'	1934'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from 4200 feet  
to 4 feet for each plug set.

12-27, Pumped 25 sks. cem. to 4200'. 12-28, Shot pipe @ 3519'. 12-29, Pumped stubb  
plug w/25 sks. cem. to 3519'. 12-30, Shot pipe @ 1934'. Pumped 70 sks. cem. to 1020'.  
Pumped 40 sks. cem. to 700'. Capped w/10 sks. cem. form 34'-4'. Welded on steel plate  
w/name & date using 9.5 lbs. 38 visc. mud between plugs.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mike Proctor's Casing Pullers, Inc.  
3022 NW Expwy, #305, Okla. City, OK 73112

STATE OF Texas COUNTY OF Potter, ss.  
R. E. Mathis ((employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. E. Mathis  
P.O. Box 2009/Amarillo, TX 79189  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 1983

My Commission expires: 4/13/85

Jan Rogers  
Notary Public.