

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt

County. Sec. 2 Twp. 26 Rgc. (E) 12 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NE Cor. S/2 Lat 2. NE 1/4

Lease Owner Lion Oil Refining Co.

Lease Name Sadie

Well No. 1

Office Address El Dorado, Ark.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Oct. 19 19 43

Application for plugging filed ✓ 19 43

Application for plugging approved ✓ 19 43

Plugging commenced ✓ 19 43

Plugging completed ✓ 20 19 43

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. J. Alexander

Producing formation Depth to top Bottom Total Depth of Well 4350 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 7/8"	2:93'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud pumped in up to 300'. Plug set at 248', using 15 sacks cement. Plug set at 26' - 10 sacks cement

PLUGGING
FILE SEC 2 26 12W
BOOK PAGE 94 LINE 45



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lion Oil Refining Co.
Address El Dorado, Ark.

STATE OF _____, COUNTY OF _____, ss.

_____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Simon Hayer

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of November 1943

Ruth Rickerbrook
Notary Public.

My commission expires Nov 4, 1943




Sadie #1
N 1/2 Lot 2 in NE/4 of Section 2 -- 5-12W
Pratt County, Kansas
Lion Oil Refining Company

Commenced: Sept. 22, 1943
 Completed: Oct. 20, 1943

Surface clay	0	15	: Kinderhook shale and cherty lime	4080	4108
Sand	15	160	Shale	4108	4124
Red bed and sand	160	240	Shale (Kinderhook)	4124	4158
Sand and shale	240	337	Viola lime (cherty)	4158	4166
Red bed	337	480	Lime (cherty)	4166	4173
Sand	480	750	Shale, lime and chert	4173	4177
Shale	750	810	Lime and chert	4177	4196
Shale and shells	810	890	Lime, cherty	4196	4217
Sand	890	990	Shale	4217	4241
Shale	990	1035	Simpson sand	4241	4243
Shale and shells	1035	1210	Sand	4243	4248
Shale	1210	1260	Sand and shale	4248	4296
Salt, shale and shells	1260	1310	Dolomite (Arb.)	4296	4350
Shale and shells	1310	1400			
Streaks of sand	1400	1572	TOTAL DEPTH		4350
Shale, shells and sand	1572	1640			
Lime and shale	1640	1735			
Sand and lime	1735	1820			
Sandy lime	1820	1920			
Shale and lime	1920	1950			
Lime and sand	1950	2030			
Shale	2030	2055			
Shale and shells	2055	2065			
Sandy lime	2065	2175			
Lime and shale	2175	2325			
Lime	2325	2380			
Lime and shale	2380	2505			
Lime	2505	2545			
Lime and shale	2545	2610			
Shale and shells	2610	2670			
Shale and lime	2670	2870			
Lime	2870	2900			
Broken lime	2900	2985			
Shale	2985	3050			
Lime and shale	3050	3100			
Lime	3100	3120			
Broken lime	3120	3190			
Lime	3190	3335			
Broken lime	3335	3395			
Lime	3395	3420			
Broken lime	3420	3470			
Shale and lime	3470	3500			
Lime	3500	3546			
Lime and shale	3546	3644			
Lime and streaks of shale	3644	3680			
Lime and shale	3680	3719			
Lime	3719	3923			
Lime and shale breaks	3923	3974			
Lime	3974	3983			
Chat	3983	3988			
Shale (little chert)	3988	4010			
Chert (broken)	4010	4032			
Shale	4032	4034			
Cherty lime	4034	4042			
Shale	4042	4052			
Chert	4052	4064			
Chert and shale	4064	4080			

CASING RECORD

3-5/8" Casing set at 295' and cemented with
 175 sacks of cement.



PLUGGING
 FILE SEC 2 260.124
 BOOK PAGE 94 LINE 45

COUNTY OF TULSA)
 I hereby affirm that the above and foregoing is a true and correct copy of the log of your Sadie Well #1, located in the Northeast Corner of the South Half of Lot 2, in the Northeast Quarter of Section 2, Township 26 South, Range 12 West, Pratt County, Kansas.

HELMERICH & PAYNE, INC.

By [Signature]
 Secretary

Subscribed and sworn to before me, a Notary Public, this 28th day of October, 1943.

My commission expires July 22nd, 1947

[Signature] Notary Public