

15-151-00075-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

PRATT County. Sec. 6 Twp. 26 Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines. SWc Lot 3
Lease Owner Musgrove Petroleum Corp., Inc.
Lease Name Swinger Well No. 1
Office Address Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 4/10/56 19
Application for plugging filed 4/9/56 19
Application for plugging approved 4/9/56 19
Plugging commenced 4/10/56 19
Plugging completed 4/10/56 19
Reason for abandonment of well or producing formation dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	295	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Filled hole with mud to 290'. Set first plug using 1/4 sks hulls and 20 sks cement through drill pipe. Filled hole with mud to 38'. Set 2nd plug using 1/4 sks hulls and 10 sks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.
Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker

(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of April, 1956

My commission expires 1-30-57

Margie Cooper Notary Public.

PLUGGING
FILE SEC 6 T 26 R 12W
BOOK PAGE 52 LINE 48

4-12-56

MUSGROVE PETROLEUM CORP., INC.
Swinger #1

SWc Lot 3-Sec 6-26S-12W
Pratt County, Kansas

Trans Era Petroleum, Inc.-Contr.

Elev: 1895 GL
1900 KB
1897 DF

Total Depth: 4350'

Comm: 3/26/56
Comp: 4/10/56

Casing:

8 5/8 @ 295

Cement:

225 sks (2% Gel 2 cc)

FORMATION	DEPTH
Sandy, red rock	35
Sand	170
Shale & shells	295
Red bed	720
Anhydrite	735
Shale & shells	1100
Salt & shale & gyp	1140
Sand	1149
Shale & shells	1650
Lime	1778
Lime & shale	1940
Shale & gyp	2060
Lime & shale	2291
Shale & shells	2450
Shale, lime streaks	2570
Shale, shells & lime	2756
Sandy shale	2890
Lime	2936
Shale, lime streaks	3066
Shale & lime	3188
Lime	3254
Lime & shale	3402
Lime	3490
Lime & shale	3548
Sand & shale	3585
Shale & lime	3717
Lime	3758
Lime & shale	3828
Lime	3874
Lime & shale	3919
Lime	3999
Shale & lime	4051
Lime, shale & chert	4083
Chert	4110
Chert & shale (Black)	4205
Simpson shale & sand	4240
Sand & shale	4280
Shale & chert	4298
Lime & shale	4344
Arb.	4350
Tops: Heebner shale	3473
Toronto lime	3493
Douglas shale	3548
Lans. K. C.	3659
Miss.	4080
Arb.	4350

PLUGGING
 WELL SEC 6 T 26 R 12W
 BOOK PAGE 52 LINE 45

APR 12 1956
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

Subscribed and sworn to before me this 11th day of April, 1956.

My commission expires: 1-30-57.

C. D. Honaker
Margie Cooper
 Notary Public