

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-151-21487-0000

API NUMBER COMPLETED 1-24-84

LEASE NAME KELLER

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 8 TWP 26 RGE. 12 (N) or (W)

COUNTY PRATT

Date Well Completed 1-24-84

Plugging Commenced 11-14-88

Plugging Completed 11-29-88

LEASE OPERATOR CONSERVATION DIVISION HEALTH PETROL. CORP.

ADDRESS P.O. Box 2458 HUTCHINSON, KS. 67504

PHONE (316) 463-5461 OPERATORS LICENSE NO. 3243

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DODGE CITY, KS.

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4405'

Show depth and thickness of all water, oil and gas formations. PERFS: 2996-3050 PBD-3085'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	253	8 5/8	253'	0
		0	3100	5 1/2	3100	1812'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

11-14-88: SAND TO 50' ABOVE PERFS- 5 SX. CEMENT ON TOP.

11-25-88: SHOT OFF AND PULLED 1812' OF 5 1/2 CSG.

11-29-88: HALCO HOOKED UP TO 8 5/8- PUMPED 4 SX. HULLS- 10 SX GEL- 50 SX. CEMENT- 10 SX GEL- 2 SX HULLS- RELEASED PLUG- 100 SX. CEMENT.

ISIP ON (If additional description is necessary, use BACK of this form.)

VACUUM.

Name of Plugging Contractor PRATT WELL SERVICE, Inc. License No. 5893

Address P.O. Box 847 PRATT, KS. 67124

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) P.O. Box 847- Pratt, KS.



SUBSCRIBED AND SWORN TO before me this 30th day of November, 19 88

Dorothy M. Furgason
 Notary Public

My Commission Expires: February 6, 1989