

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20,569-00-00

LEASE NAME Baker

WELL NUMBER 1-34

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section L

1980 Ft. from E Section L

SEC. 34 TWP. 33 RGE. 20 ~~W~~ or

COUNTY Comanche

LEASE OPERATOR Bishop Operating Co, Inc.

ADDRESS P.O. Box 1807 - Hutchinson, Kansas 67504

PHONE# (316) 662-6445 OPERATORS LICENSE NO. 30972

Date Well Completed 7-14-82

Character of Well Oil

Plugging Commenced 2-2-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10:00 AM

The plugging proposal was approved on 2-2-93 (date)

by Richard Lacy (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation LKC Depth to Top 4743 Bottom 4761 T.D. 4820

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	684	0
				5 1/2	4819	3364

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from ___ feet to ___ feet each

Bottom plug: Sanded to 4675 & bailed 5 sx Cement.

Top plug: 300 lb Hulls, 10 sx Gel, 50 sx Cement, 10 sx Gel, 100 lb Hulls, wiper plug, 125 sx Cement, 60/40 with 6% Gel. Had maximum pressure of 600 lbs, and shut in pressure of 300 lbs

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bishop Operating Co, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke


(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary G. Burke Pres

(Address) Box 251, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 3 day of February, 1993



My Commission Expires: 4-30-96

Anna K. Burke
Notary Public

Notary Public - 4 1993

RECEIVED
FEBRUARY 1993
CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
Revised 10