

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 033-20789-0000 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR W. C. Payne OPERATOR'S LICENSE NO. 30431

ADDRESS 800 United Founders Tower, OKC, OK 73112 PHONE # (405) 843-9419

LEASE (FARM) Betty-Jean WELL NO. 1-11 WELL LOCATION SWNE COUNTY Comanche

SEC. 11 TWP. 35S RGE. 17W ~~or~~ (W) TOTAL DEPTH 6750' PLUG BACK TD 5725'

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8" SET AT 708' CEMENTED WITH 400 SACKS

CASING SIZE 4-1/2" SET AT 5725' CEMENTED WITH 175 SACKS

PERFORATED AT 5552-5596 CIBP @ 5520' 5424-28

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Top of cmt @ 5010', set CIBP @ 5100'. Shoot 4-1/2" off

@ 4900'. Spot 100' cmt plug. Pull 4-1/2 to 758'. Circulate 100' plug from 758'

to 658'. Pull 4-1/2, spot 30' plug in top of 8-5/8". Weld on cop.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? \_\_\_\_\_  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3 to 4 weeks

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Clyde D. Towery PHONE # (405) 843-9419

ADDRESS 800 United Founders Tower, OKC, OK 73112

PLUGGING CONTRACTOR Clarke Corp. LICENSE NO. 5105

ADDRESS 107 W. Fowler, Box 187 PHONE # (316) 886-5665  
Medicine Lodge, KS 67104

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED:  
SEP 17 1990  
9-17-90  
DATE:

Clyde D. Towery  
(Operator/Agent) Clyde D. Towery  
September 14, 1990



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
 KEITH R. HENLEY CHAIRMAN  
 RICH KOWALEWSKI COMMISSIONER  
 JACK SHRIVER COMMISSIONER  
 JUDITH MCCONNELL EXECUTIVE DIRECTOR  
 FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION  
 SHARI FEIST ALBRECHT, DIRECTOR  
 200 Colorado Derby Bldg.  
 202 W. 1st Street  
 Wichita, KS 67202-1286  
 (316) 263-3238

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

September 18, 1990

W.C. Payne  
 800 United Founders Tower  
 Oklahoma City, OK 73112

Betty-Jean #1-11  
 SW NE 11-35-17W  
 Comanche County, KS  
 API No. 15-033-20,789-0000

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams  
 Production Supervisor

District: #1, 304 W. McArtor  
 Dodge City, KS 67801  
 (316) 225 - 6760