

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERRY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-151-21089-00-00

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Thomas 1-25

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C NW NE

SEC. 25 TWP. 26S RGE. 15W (E) OR (W)

COUNTY Pratt

DATE WELL COMPLETED \_\_\_\_\_

PLUGGING COMMENCED 9-1-83

PLUGGING COMPLETED 9-20-83

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947 Pratt, Kansas 67124

PHONE #( ) \_\_\_\_\_ OPERATORS LICENSE NO. \_\_\_\_\_

CHARACTER OF WELL  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACG-1 FILED? \_\_\_\_\_ IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION \_\_\_\_\_ DEPTH TO TOP \_\_\_\_\_ BOTTOM \_\_\_\_\_ T.D. 4701'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	420'	none
				4-1/2"	4683'	2159'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Pumped bottom with 70 bbl. water, 35 sacks cement and pumped plug to 3900'. Shot casing @3500', 3300', 3007', 2723', 2478', 2310', 2167' and pulled a total of 54 joints (2159') of 4-1/2" casing. Plugged well with 4 hulls, 11 gel, 50 sacks 60/40 pos, 3% gel, 2% cc. 10 gel, released plug and displaced with 100 sacks 60/40 pos, (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) 3%ge, 2%cc. Plugging Complet.

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE No. 6050  
ADDRESS Box 347 Chase, Kansas 67524


STATE OF Kansas COUNTY OF Rice, SS.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso  
(ADDRESS) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 21 DAY OF Sept., 19 83

Irene Hoover  
NOTARY PUBLIC



MY COMMISSION EXPIRES: \_\_\_\_\_

RECEIVED STATE CORPORATION COMMISSION FORM CP-4 REVISED 06-83

SEP 22 1983

CONSERVATION DIVISION  
Wichita, Kansas