

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pratt County. Sec. 26 Twp. 26S Rge. 15 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE  
Lease Owner Mull Drilling Co., Inc.  
Lease Name Mc Ahren No. 1 Well No.  
Office Address 670 1/2th National Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 24 19 58  
Application for plugging filed December 24 19 58  
Application for plugging approved December 24 19 58  
Plugging commenced December 24 19 58  
Plugging completed December 24 19 58  
Reason for abandonment of well or producing formation no oil in commercial quantities  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 1463 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	830'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 300'. Set Plug #1 at 300' cemented with 20 sacks cement.  
Filled hole with extra heavy rotary mud from Plug #1 to 35'. Set Plug #2 at 35' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 6 1959

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 29 1958

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling Inc.  
Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol  
814 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of December, 19 58

Colleen Chapple  
Colleen Chapple Notary Public.

My commission expires 11-22-62

PLUGGING  
FILE SEC 26 T 26 R 15W  
BOOK PAGE 6 LINE 25

ROTARY DRILLING LOG

OPERATOR: Mull Drilling Co., Inc.  
 McAhren No. 1  
 SW SW NE 26-26S-15W  
 Pratt County, Kansas

CONTRACTOR: Prime Drilling Company  
 COMM: 12-11-58  
 COMP: 12-24-58

Formations:

Remarks: Set 8-5/8" surface casing  
 at 830' cemented with 800 sacks Pozmix  
 2% c. c.

Sand	340'
Red Bed	620'
Sand & Shale	730'
Shale	830'
Red Bed	1170'
Shale	1580'
Shale & Shells	1935'
Lime & Shale	2105'
Lime	2225'
Lime & Shale	3563'
Lime & Shale & Chalky Lime	3710'
Chalky Lime & Shale	3845'
Lime & Shale	3937'
Lime	4357'
Lime & Chert	4382'
Core #1	4411'
Lime	4422'
Shale, Chert & Lime	4452'
Lime	4463'
Rotary Total Depth (D&A)	4463'

We certify the above log is true  
 and correct to the best of our  
 knowledge and belief.

CAPITT DRILLING INC.

*R. R. McNicol*

R. R. McNicol

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 29 1958  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING ✓  
 FILE SEC. 26 T. 26 R. 15W  
 BOOK PAGE 6 LINE 25