


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Pratt County. Sec. 26 Twp. 26S Rge. 15W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW SW SE

Lease Owner Zenith Drilling Corporation, Inc.
Lease Name Lincoln Land #2 Well No. 2
Office Address Suite 600, 200 West Douglas, Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed February 26, 19 78
Application for plugging filed February 25, 19 78
Application for plugging approved February 25, 19 78
Plugging commenced 12:30 AM, February 26, 19 78
Plugging completed 2:30 AM, February 26, 19 78
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4525'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	391'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Pumped thru open ended drill pipe -
40 sacks at 540' and 40 sacks at 390',
Solid Bridge with plug and 1/2 sack Hulls
at 40' with 12 sacks to surface. 3 sacks
in rathole.

RECEIVED
STATE CORPORATION COMMISSION

MAR 03 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
P. O. Box 129, Sterling, Kansas

STATE OF KANSAS COUNTY OF RICE SS.
Richard L. Mead (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) Richard L. Mead
Richard L. Mead, Vice President
P. O. Box 129, Sterling, Kansas 67579
(Address)

Subscribed and Sworn to before me this 27th day of February, 19 78

My commission expires 

Bernard Laudermilk
Bernard Laudermilk, Notary Public.

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - LINCOLN LAND #2
Located: NW SW SE, Section 26-26S-15W, Pratt County
Kansas

OWNER: Zenith Drilling Corporation, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 10, 1978
COMPLETED: February 26, 1978

TOTAL DEPTH: 4525'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 375 Sand and Clay, Shale	Ran 9 joints new 30 and 33#, 10 3/4" casing, 380.15' set at 391' K.B. with 325 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 7:45 PM, 2-10-78, by Howco.
375 - 395 Shale	
395 - 1003 Shale and Red Beds	
1003 - 1021 Anhydrite	
1021 - 1857 Shale	
1857 - 2000 Shale and Shells	
2000 - 4377 Shale and Lime	
4377 - 4394 Lime, Chert and Shale	
4394 - 4420 Chert	
4420 - 4477 Lime and Shale	
4477 - 4495 Sand, Cherty Lime	
4495 - 4525 Lime, Chert, Shale	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

MAR 03 1978

CONSERVATION DIVISION
Wichita, Kansas