

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County. Sec. 26 Twp. 26S. Rge. 15W. (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. SE/ $\frac{1}{4}$ SE/ $\frac{1}{4}$ SE/ $\frac{1}{4}$

Lease Owner Basin Oil Company

Lease Name Margaret Carver Robbins Well No. 1

Office Address 1909 First National Building, Oklahoma City, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 29, 1956

Application for plugging filed January 29, 1956

Application for plugging approved January 29, 1956


Plugging commenced January 29, 1956

Plugging completed January 29, 1956

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas

Producing formation Arbuckle Lime Depth to top 4700 Bottom 4720 Total Depth of Well 4720 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	808'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole within 600 feet of top. Pushed Halliburton plug to same and cemented with 20 sacks of cement. Filled hole with mud to within 40 feet. Cemented on top with 10 sacks cement to surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Basin Oil Company
Address 1909 First National Building
Oklahoma City, Oklahoma

STATE OF Kansas, COUNTY OF Pratt, ss.
Doyle Clark (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Doyle Clark

(Address)

SUBSCRIBED AND SWORN to before me this 6th day of February, 1956

Kristanderson Notary Public.

My commission expires February 15, 1958



COMPANY: Basin Oil Company
 FARM: Robbins No. 1
 Total Depth: 4720
 Commenced: January 11, 1956
 Completed: January 29, 1956
 Contractor: Larson Drilling Company

Location: 0 SE SE SE
 Sec. 26-269-15W,
 Pratt County, Kansas
 Elevation: 2041 D.F.
 Production: D & A
 Casing: 808' w/750 sx Pozmix
 12 sx c.c. 60# Flocele
 mixed w/250 sx cement

Figures Indicate Bottom of Formations

	Tops:
311 Sand & Shale	Heebner 3750
1750 Sand, Shale & Lime	Brown lime 3909
2085 Sand, Shale & Lime	Lansing KC 3937
2382 Sand, Shale & Lime	Base KC 4261
2595 Sand	Mississippi 4410
2894 Shale & Lime	Kinderhook 4429
3227 Lime & Shale	Kinderhook Sand 4459
3550 Lime & Shale	Viola 4537
3759 Lime	Simpson 4595
3850 Lime & Sand	Arbuckle 4680
3929 Sand	RTD 4720
4231 Lime	
4455 Lime & Shale	
4535 Sand	
4620 Lime & Chert	
4720 Lime	

D & A

State of Kansas)
 COUNTY of Pratt) SS

I, Doyle Clark of the Larson Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Robbins #1 well.

Doyle Clark

Subscribed and sworn to before me this 6th day of February, 1956.

My Commission Expires February 15, 1958

Kinderhook
 Notary Public

PLUGGING
 FILE SEC. 26-26-15W
 BOOK PAGE 35 LINE 12