

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt County. Sec. 28 Twp. 26S Rge. 15 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NW/4, NW/4, NE/4

Lease Owner Amerada Petroleum Corporation

Lease Name Taylor-Mowbray Unit Well No. 1

Office Address Box 197 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-7- 1955

Application for plugging filed 2-7- 1955

Application for plugging approved 2-7- 1955


Plugging commenced 2-7- 1955

Plugging completed 2-8- 1955

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Warren Horner of Great Bend, Kans.

Producing formation Depth to top Bottom Total Depth of Well 4540' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 392' | None. |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud to 300' from top - set 1/3 sack hulls & bridge plug at 300' - spotted 20 sacks cement thru drill pipe - filled hole with heavy mud to 35' from top - set 1/3 sack hulls & bridge plug at 35' - mixed & dumped in 10 sacks cement filling surface casing to top. Well plugged & abandoned 2-8-55 as required by State Pluggger Mr. Warren Horner of Great Bend, Kansas.

RECEIVED
COMMISSION
FEB - 9 1955
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barbour Drilling Co.
Address 1st Nat'l. Bldg. - Tulsa, Oklahoma

STATE OF _____, COUNTY OF _____, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
Box 197 - Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of February, 1955

Notary Public.

My commission expires July 29, 1957


PLUGGING
FILE SEC 28 TWP 26S R 15W
BOX PAGE 96 LINE 9

WELL LOG

Taylor-Mowbray Unit #1 - NW/4, NW/4, NE/4 - Sec. 26 - 26S - 15W
Pratt County, Kansas

| | | |
|-------|----------|-----------------------|
| 0' | to 160' | - Sand & Shale. |
| 160' | to 600' | - Shale & Sand. |
| 600' | to 1010' | - Shale & Shells. |
| 1010' | to 1060' | - Anhydrite. |
| 1060' | to 1900' | - Shale & Shells. |
| 1900' | to 2355' | - Shale & Lime. |
| 2355' | to 2368' | - Sand. |
| 2368' | to 2495' | - Lime & Shale. |
| 2495' | to 3360' | - Shale & Lime. |
| 3360' | to 3455' | - Sandy Lime & Shale. |
| 3455' | to 3585' | - Shale & Lime. |
| 3585' | to 3940' | - Lime & Shale. |
| 3940' | to 4205' | - Lime. |
| 4205' | to 4260' | - Lime & Shale. |
| 4260' | to 4425' | - Lime. |
| 4425' | to 4465' | - Shale & Lime. |
| 4465' | to 4479' | - Lime & Chert. |
| 4479' | to 4540' | - Lime. |

T. D. = 4540'



RECEIVED
STATE CORPORATION COMMISSION

FEB -9 1935

REGISTRATION DIVISION
KANSAS CITY, MO