

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pratt SEC. 29 TWP. 26s RGE. 15 E/W  
Location as in quarters or footage from lines:  
C SE SE

|  |  |    |   |
|--|--|----|---|
|  |  |    |   |
|  |  |    |   |
|  |  | 29 |   |
|  |  |    | 4 |

Locate Well  
correctly on above  
Section Platt.

Lease Owner Texas Energies, Inc.  
Lease Name State of Kansas Well No. 1-29  
Office Address Box 947 Pratt, KS 67124  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 3-07-82  
Application for plugging filed 3-22-82  
Plugging commenced 3-07-82  
Plugging completed 3-07-82  
Reason for abandonment of well or producing formation  
Dry Hole

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Morris Leslie  
Producing formation -- Depth to top --- bottom -- T.D. 4745

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

| Formation | Content | From | To | Size  | Put in | Pulled Out |
|-----------|---------|------|----|-------|--------|------------|
| None      |         |      |    | 8 5/8 | 450'   | None       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from    feet  
to    feet for each plug set.

Plugged well with 130 sxs 50-50 poz mix 3% CC 2% Gel as follows:  
Cement plug @ 600' with 60 sxs  
Cement plug @ 270' with 40 sxs  
Cement plug @ 40' with 10 sxs  
rathole with 10 sxs  
mousehole with 10 sxs

STATE CORPORATION COMMISSION  
**MAR 23 1982**  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Texplor Drilling

STATE OF Kansas COUNTY OF Pratt, ss.  
E. H. Bittner (employee of owner) or ~~owner or operator~~ of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) E.H Bittner  
Box 947 Pratt, KS 67124  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 19 82

My Commission expires: April 23, 1983



Darlene Bittner  
Notary Public.

