

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County, Sec. 29 Twp. 26S Rge. 15W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW NW

Lease Owner Tomlinson & Kathol

Lease Name Tatlock Well No. 1

Office Address 1125 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 8/14 19 64

Application for plugging filed 8/14 19 64

Application for plugging approved 8/14 19 64

Plugging commenced 8/14 19 64

Plugging completed 8/14 19 64

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes Elving

Name of Conservation Agent who supervised plugging of this well None

Producing formation None Depth to top Bottom Total Depth of Well 4690 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| Surface | | | | 8-5/8" | 346' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud was put into the hole from 4690' to 250' where the bottom plug was set and cemented with 25 sacks cement. Mud was again put into the hole to a depth of 40 feet where the top plug was set and cemented with 10 sacks cement. The rathole was plugged with 2 sacks cement. Surface casing was cut off below ground level and the location abandoned.

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1964
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Tomlinson & Kathol (If additional description is necessary, use BACK of this sheet)
Address 1125 Wichita Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Richard C. Davis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein, contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard C. Davis
1125 Wichita Plaza (Address)

SUBSCRIBED AND SWORN to before me this 17th day of August, 19 64

My commission expires Jan. 19, 1965
Esther Lamone Notary Public

DRILLERS LOG
 TOMLINSON & KATHOL
 # 1 TATLOCK
 C NW NW, SEC. 29-26S-15W
 PRATT COUNTY, KANSAS

Contractor - Tomlinson & Kathol

Commenced: 7/27/64
 Completed: 8/14/64
 Elevation: 2059 KB

| <u>From</u> | <u>To</u> | <u>Description</u> | <u>Remarks</u> |
|-------------|-----------|--------------------|----------------------------------|
| 0 | 340 | Surface Hole | |
| 340 | 490 | Rathole - Shale | 346' 8-5/8" Surface Casing w/275 |
| 490 | 1099 | Shale & Shells | sacks cement |
| 1099 | 2444 | Shale | |
| 2444 | 2879 | Lime & Shale | |
| 2879 | 3370 | Shale | |
| 3370 | 3613 | Lime & Shale | |
| 3613 | 3852 | Shale & Lime | |
| 3852 | 3914 | Lime & Shale | |
| 3914 | 3958 | Shale & Lime | |
| 3958 | 4018 | Lime & Shale | |
| 4018 | 4111 | Lime | |
| 4112 | 4291 | Lime & Shale | |
| 4291 | 4355 | Lime | |
| 4355 | 4472 | Lime & Shale | Heebner 3756 |
| 4472 | 4585 | Lime | Douglas 3798 |
| 4585 | 4625 | Lime & Shale | Lansing-K.C. 3924 |
| 4625 | 4664 | Shale | Base K.C. 4246 |
| 4064 | 4690 | Shale w/lime | Kinderhook 4352 |
| 4690 | | Rotary Total Depth | Viola 4408 |
| | | | Simpson 4594 |
| | | | Arbuckle 4662 |

RECEIVED
 STATE CORPORATION COMMISSION

AUG 19 1964

CONSERVATION DIVISION
 Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.



 Richard C. Davis

STATE OF KANSAS

SS

COUNTY OF SEDGWICK

Subscribed and sworn to before me this 17th day of August, 1964.


 Esther Lamone, Notary Public

My Commission Expires: Jan. 19, 1965