

LEASE NAME Wood

WELL NUMBER #1

SPOT LOCATION N/2 SW NW

SEC. 18 TWP. 26S RGE. 15W (E) or (W) (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 3-5-86

Plugging Completed 4-17-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Beren Corporation

ADDRESS 970 4th Financial Ctr., Wichita, Ks. 67202

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5364

Character of Well Gas
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4520'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	407'	none
				4-1/2"	4520'	1523'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from ___ feet to ___ feet each set.

Pumped bottom plug to 3600' with 1 hull and 55 sacks cement. Shot casing @1523' and pulled a total of 38 joints (1523') of 4-1/2" casing. Plugged surface with 5 hulls, 100 sacks econolite w/1/2 lb. flow seal. (Pipe was Collapsed @1550')
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
 Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso
 (Address) Box 347 Chase, Ks. 67524

APR 24 1986
 CONSERVATION DIVISION
 Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 22 day of April, 1986

Irene Hoover
 Notary Public

My Commission expires: _____



CONTRACTOR'S WELL LOG

OPERATOR: Beren Corporation
CONTRACTOR: Union Drilling Co., Inc.
WELL NAME: #1 Wood
LOCATION: C N/2 SW NW Section 18-26S-15W
Pratt County, Kansas
COMMENCED: February 10, 1978
COMPLETED: February 28, 1978

0	2045	Shale	Set 8-5/8" at 407' with 350 sx.
2045	2165	Lime and shale	
2165	2235	Lime	
2235	2259	Shale	
2259	3353	Lime and shale	
3353	4355	Lime	
4355	4375	Chert	
4375	4444	Lime	
4444	4520	Chert	
	4520	T. D.	

We certify that the above and foregoing is a true and correct copy of the log on the #1 Wood, C N/2 SW NW, Section 18-26S-15W, Pratt County, Kansas.

UNION DRILLING CO., INC.


R. D. Messinger

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the sforesaid County and State as of this 1st day of March, 1978.



Donna F. Brown - Notary Public

My commission expires:
7-29-78

STAT. SEC. DIVISION
JAN 25 1983
CONSERVATION DIVISION