


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Pratt County. Sec. 23 Twp. 26S Rge. 15W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
S/2 S/2, SE $\frac{1}{4}$

Lease Owner Zenith Drilling Corporation, Inc.
Lease Name Jackson #1 Well No. 1
Office Address Suite 600 - 200 West Douglas, Wichita, Ks 672
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed March 6, 1978 19
Application for plugging filed March 6, 1978 19
Application for plugging approved March 6, 1978 19
Plugging commenced 1:00 PM, March 6, 1978 19
Plugging completed 3:15 PM, March 6, 1978 19
Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 1430'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	374'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Filled hole with heavy mud. Pumped thru
open ended D.P. 40 sacks 540' and 40 sacks
at 360'. Solid bridge with plug and 1/2
sack hulls at 40' and 20 sacks to surface.
3 sacks in rathole.

RECEIVED
STATE CORPORATION COMMISSION

MAR 09 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY
P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE ss.


F. A. Wuellner (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature)

F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

Subscribed and Sworn to before me this 7th day of March 1978

My commission expires



Charles M. Hall,

Notary Public.

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - JACKSON #1
Located: C S/2 S/2 SE/4, Section 23-26S-15W, Pratt County,
Kansas

OWNER: Zenith Drilling Corporation, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 27, 1978
COMPLETED: March 6, 1978

TOTAL DEPTH: 4430'

LOG

0 - 377 Sand, Clay, Red Bed
377 - 1011 Shale, Sand and Red Beds
1011 - 1024 Anhydrite
1024 - 1044 Shale
1044 - 1745 Shale, Lime Stgs, Salt
1745 - 4193 Lime and Shale
4193 - 4270 Lime, Cherty Lime and Shale
4270 - 4350 Lime
4350 - 4380 Lime and Shale
4380 - 4390 Shale and Chert
4390 - 4420 Lime, Shale and Chert
4420 - 4430 Cherty Lime

CASING RECORD

Ran 9 joints new 30# and 33#, 10 3/4" casing, 362.65' set at 374' K.B. with 325 sacks 60/40 Pozmix with 3% cc. Plug down at 3:30 PM, 2-27-78, by Howco.

Plugged.

RECEIVED
STATE OF KANSAS
MAR 09 1978