

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, Kansas 67202

RECEIVED Form CP-4
STATE CORPORATION COMMISSION 12-15-80

IAN 13 1983

WELL PLUGGING RECORD

CONSERVATION DIVISION
Wichita, Kansas

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 23 TWP. 26S RGE. 15 E/W
Location as in quarters or footage from lines:
C W/2 W/2 W/2

Lease Owner Vincent Oil Corporation
Lease Name Jackson Well No. #1
Office Address 125 N. Market Suite 1110 Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed 1-2-83
Application for plugging filed 1-2-83
Plugging commenced 1-2-83
Plugging completed 1-2-83
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom T.D. 4429'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	450'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Spotted 70 sx. cement @ 900' thru drill pipe.
Spotted 40 sx. cement @ 440' thru drill pipe.
Solid bridge plug @ 40', Spotted 10 sx. cement thru drill pipe.
Spotted 10 sx. cement in rathole thru drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.


Ernest Sifford (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.


(Signature) Ernest Sifford
401 E. Douglas #500 Wichita,
(Address) Ks. 67202

SUBSCRIBED AND SWORN TO before me this 11th day of January, 1983

Carolyn J. Tjaden
Notary Public.

My Commission expires:





RECEIVED
STATE CORPORATION COMMISSION

WHITE

JAN 13 1983

AND ELLIS DRILLING, Inc.

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

OPERATOR: Vincent Oil Corporation 125 N. Market Suite 1110 Wichita, Kansas 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Jackson Well No. #1

Sec. 23 T. 26S R. 15W Spot C W/2 W/2 W/2

County Pratt State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 450' with 324 sx. 6% gel
3% cc

Production: _____ @ _____ with _____ sx.

Type Well: D&A Total Depth 4429'

Drilling Commenced 12-17-82 Drilling Completed 1-2-83

Formation	From	To	Tops
Cellar	0	7	
Sand	7	1083	
Shale, Lime	1083	1877	
Shale, Lime, Sand	1877	1977	
Shale, Lime	1977	3937	
Lime	3937	4110	
Shale, Lime	4110	4429	