

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,082-00-00

LEASE NAME Lutes #1-36

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER C S/2 NW

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 36 TWP. 26s RGE. 15w (E) or (W)

COUNTY Pratt

Date Well Completed

Plugging Commenced 4/3/85

Plugging Completed 4/9/85

LEASE OPERATOR Texas Energies, Inc.

ADDRESS Box 947, Pratt, Ks. 67124

PHONE# (316) 672-7581 OPERATORS LICENSE NO. 5087

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom RECEIVED 4736'

Show depth and thickness of all water, oil and gas formations.

STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

APR 17 1985

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	406'	none
				4 1/2"	4690'	2022'

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran 60 bbls salt water to kill well. Plugged bottom with 1 sack hulls, & 50 sacks cement & pushed to 4000'. Shot pipe at 3900', 3500', 3000', 2700', 2500', 2200', & 2022'. Pulled 50 joints. Plugged well with 4 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8 5/8 plug, & 150 sacks 60/40 poz 2% gel 3% c.c. Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso CASing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 16th day of April, 1985

James Hoover
Notary Public

My Commission Expires:

