

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt County, Sec. 32 Twp. 26S Rge. 15 (X) (W)

Location as "NE/CNW/SW" or footage from lines 240' FEL & 320' FNL of NW/4

Lease Owner Bell Oil & Gas Co. & Honaker-Davis Drlg. Co.

Lease Name Tatlock Ranch "A" Well No. 1

Office Address 2008 Lakin, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-26 19 56

Application for plugging filed 8-26 19 56

Application for plugging approved 8-26 19 56

Plugging commenced 8-26 5:00 P.M. 19 56

Plugging completed 8-26 7:00 P.M. 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Telephone to Mr. Merle Reeves

Name of Conservation Agent who supervised plugging of this well Mr. Merle Reeves

Producing formation Depth to top Bottom Total Depth of Well 4705 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1043	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy rotary mud to 300'. Set plug with 1/3 sack hulls and 20 sacks cement thru drill pipe.

Filled hole to 35' with heavy rotary mud. Set plug with 1/3 sack hulls and 10 sacks cement-cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Honaker-Davis Drlg. Co.

Address 2008 Lakin, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Bill Edwards (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Edwards

2008 Lakin, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August 19 56

My commission expires 6-25-59

Kenneth G. Fischer Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 32 T. 26 R. 15 W.
BOOK PAGE 93 LINE 35

AL 32 26
CONSERVATION DIVISION
Wichita, Kansas


DRILLERS LOG

Tatlock Ranch "A" No. 1
Loc: 240' FEL & 330' FNL of NW/4
Sec: 32-26S-15W
Pratt County, Kansas
Company: Honaker-Davis Drig. Co., et al
Contractor: Honaker-Davis Drig. Co.

Comm: 8- 9-56
Comp: 8-26-56
Rotary Total Depth: 4705'
Casing: 8-5/8" at 1043
D & A.


0	185	Sand & Gravel	
185	405	Blue Shale	
405	460	Shale	
460	600	Red Bed	8-5/8" casing cemented
600	690	Sand	at 1043' with 525 sacks
690	1034	Red Bed & Shale	cement and 5 sacks
1034	1060	Anhydrite	calcium chloride
1060	1210	Red Bed	
1210	1265	Red Bed & Shale	
1265	1685	Shale & Shells	
1685	1755	Lime & Shale	
1755	1995	Shale & Shells	
1995	4393	Lime & Shale	
4393	4439	Lime & Chert	
4439	4519	Lime & Shale	
4519	4575	Chert & Shale	
4574	4705	Lime & Shale	
4705		Total Rotary Depth	D & A

I certify that this is the true and correct copy of the above log to the best of my knowledge.



H. S. Forbes

Subscribed and sworn to before me this 27th day of August, 1956.



Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

PLUGGING
FILE SEC. 32T 26R 15W
BOOK PAGE 93 LINE 35

1956
AUG 28