

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21-109-00-00

LEASE NAME Moore Trust A

WELL NUMBER 1

NWSE Ft. from S Section Line

 Ft. from E Section Line

SEC. 27 TWP. 26S RGE. 14 ~~W~~ W

COUNTY Pratt

Date Well Completed (?)

Plugging Commenced 5/22/85

Plugging Completed 5/29/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pickrell Drilling Co.

ADDRESS 110 N. Market, Suite 205, Wichita, KS 67202

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	302	None
				4 1/2	4403	2116

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug back at 4324 and C.I.B. at 3996, sand from 3996 to 3830, 4sx cement with dump bailer to 3800, ripped at 2400 and 2200, 2116, Allied pump in 3sx hulls, 15sx jell, 50sx cement, 10sx jell, 1sx hull, plug, 130sx cement, plug, 20sx cement, 60-40 POZ, 2% jell, 3% CC P. Luthie, Aumiller, M. Bland and E. Morgenstern on location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corp.

Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (Employee of Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Elmo Morgenstern*

(Address)

RECEIVED
License No. 5105
STATE CORPORATION COMMISSION

JUN 05 1985

CAREN J. McCULLOUGH
NOTARY PUBLIC
STATE OF KANSAS

My Appt. Exp. 6-29-85 SUBSCRIBED AND SWORN TO before me this 30 day of May, 19 85

Caren J. McCullough
Notary Public

My Commission Expires: June 29, 1987