


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

PRATT COUNTY, KANSAS County. Sec. 28 Twp. 26S Rge. 14W (E) (W)
Location as "NE/CNW%SW%" or footage from lines. NW NW SE
Lease Owner K & E and MUSGROVE PETROLEUM
Lease Name THOMPSON 'B' Well No. 1
Office Address 719 Union Center Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-15-57 19
Application for plugging filed 10-15-57 19
Application for plugging approved 10-15-57 19
Plugging commenced 10-15-57 19
Plugging completed 10-15-57 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Brundage
Producing formation Depth to top Bottom Total Depth of Well 4684 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	345'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole with heavy mud to 300' placed plug & hyls mixed with 20 sx cement thru drill pipe then put heavy mud to 35' set solid bridge and mixed 10 sx cement to bottom of cellar. Job Complete.

STATE CORPORATION COMMISSION
OCT 24 1957
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clinton Engstrand (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Clinton Engstrand*
Clinton Engstrand, President, K & E DRILLING, INC.
719 Union Center Building, Wichita 2, Kansas

Subscribed and sworn to before me this 22nd day of October, 1957.



11 August 1958.

Patricia M. Edwards
Patricia M. Edwards, Notary Public.

PLUGGING
FILE SEC 28 T. 26 R. 14W
BOOK PAGE 54 LINE 17

W E L L L O G

OPERATOR:	K & E DRILLING, INC. AND MUSGROVE PETROLEUM CO. 719 Union Center Building	FARM NAME:	#1 THOMPSON 'B'
CONTR:	K & E DRILLING, INC. 719 Union Center Building Wichita, Kansas	LOCATION:	NW NW SE, 28-26S-14W Pratt County, Kansas
CASING:	8-5/8" @ 388' (300 sx)	COMMENCED:	10-2-57
R.T.D.	4684'	COMPLETED:	10-14-57
		PRODUCTION:	D & A
		ELEVATION:	2005' KB

FORMATION RECORD

Depths indicate bottom of formations encountered.

Sand	235
Shale	388
Lime & Shells	394
Shale	930
Anhydrite	952
Shale	1208
Shale & Lime	1870
Lime	2880
Lime & Shale	3205
Shale & Lime	3230
Lime & Shale	3295
Lime	3754
Shale (Heeb)	3801
Sand & Shale	3880
Shale & Sand	3884
Lime (B.L.)	3916
Lime (Lsg)	3933
Lime & Shale	3997
Lime	4370
Clonglomerate	4382
Lime (Miss)	4434
Lime	4490
Chert & Lime	4530
Lime	4548
Sand & Shale	4575
Lime	4684
R.T.D.	4684

CERTIFICATION

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Clinton Engstrand, of K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the log of the #1 THOMPSON 'B' well.

Clinton Engstrand
Clinton Engstrand

Subscribed and sworn to before me this 22nd day of October, 1957.

Patricia M. Edwards
Patricia M. Edwards, Notary Public

My commission expires: 11 August 1958.

RECEIVED
STATE CORP. COMMISSION
OCT 24 1957
CONTRACTS DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 28T 26 R 14W
BOOK PAGE 54 LINE 17