



RANDLE #1

Casing Record:  
8-5/8" - 978'

Company: Metropolitan Petroleum Corp.  
Contractor: Aylward Drilling Company

Commenced: January 28, 1952  
Completed: February 17, 1952

Description:  
SE/4 SE/4 NW/4  
Sec. 30-26S-14W  
Pratt County, Kansas

D. & A.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	40	
Sand & Clay	40	150	
Sand & Shale	150	300	
Shale & Shell	300	400	
Red Bed	400	713	
Red Bed, Shale & Shells	713	960	
Shale & Shell	960	974	
Anhydrite	974	993	Set 8-5/8" casing @ 978" and cemented with 500 sax.
Shale	993	1024	
Shale & Shell	1024	1200	
Salt	1200	1305	
Shale & Shell	1305	1895	
Shale & Lime	1895	1995	
Sandy Lime	1995	2090	
Lime & Shale	2090	2545	
Lime	2545	2569	
Lime & Shale	2569	2600	
Shale	2600	2635	
Shale & Lime	2635	2905	
Shale & Shells	2905	3080	
Sandy Lime & Shale	3080	3190	
Lime & Shale	3190	3555	
Lime	3555	3630	
Lime & Shale	3630	3760	
Shale & Shells	3760	3865	
Shale & Lime	3865	3910	
Lime	3910	4260	
Shale & Lime	4260	4310	
Lime	4310	4338	
Cherty Conglomerate	4338	4365	
Conglomerate & Lime	4365	4380	
Conglomerate & Shale	4380	4420	
Shale	4420	4428	
Lime Viola	4428	4455	
Conglomerate & Lime	4455	4485	
Lime & Shale	4485	4525	
Lime	4525	4580	
Lime & Shale	4580	4630	
Arbuckle Lime	4630	4650	T.D.

TOPS: Heebner 3727  
Brown Lime 3884  
Lens. - K.C. 3910  
Small break, 3963-66, small show - Honey Comb

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FILE SEC 30 T 26 R 14 W  
BOOK PAGE 14 SUM 14

*Al Skalsky*  
Al Skalsky

Subscribed and Sworn to before me this 20th day of February, 1952.

My Commission Expires  
July 16, 1952

*Harvey Cooper*  
Notary Public