


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Phatt County. Sec. 32 Twp. 26S Rge. 14W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____
C - NE - NW
Lease Owner Hummon Oil Company
Lease Name Himphills Well No. 1
Office Address Suite 400 One Main Place, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed March 27 1978
Application for plugging filed March 30 1981
Application for plugging approved March 31 1981
Plugging commenced 4 - 23 1981
Plugging completed 5-1 1981
Reason for abandonment of well or producing formation _____
Not Productive

If a producing well is abandoned, date of last production _____
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. V. Leslie

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4437

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	332	None
				4 1/2	2980	2217

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Plug back at 2980

Dumped sand from 2980 - 2875

4 sacks - from 2875 to 2760

Ripped at 2400 - 2300 and 2217

Pulled 4 1/2' layed down

Allied pump in 10 Sacks Jell , 8- sacks Hulls - 15 sacks Jell

125 sacks 50 -50 POZ 4% Jell 3% C.C.

RECEIVED
STATE CORPORATION COMMISSION
MAY 1 1981
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barker, ss.
Elmo R. Morgenstern (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmo R. Morgenstern
Medicine Lodge, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of May, 1981

Jessie Hamilton
Notary Public.

My commission expires April 4, 1982

Hummon Oil Company - Hemphill #1
Approx. C NE NW Sec. 32-26S-14W
Pratt County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: March 18, 1978
Completed: March 27, 1978

Drillers Log

Clay	40
Sand & Clay	200
Red Bed	905
Shale & Shalle	2165
Shale	2555
Shale & Shells	2725
Shale & Lime	3005
Shale & Shells	3175
Shale & Lime	3494
Lime	3635
Lime & Shale	3755
Lime	4035
Lime & Shale	4135
Lime	4437 RTD

MAR - 9 1981
CONSERVATION DIVISION
Wichita, Kansas